



# City of Flint

## Department of Purchases & Supplies

---

Sheldon A. Neeley

TO: All Proposers  
FROM: Lauren Rowley, Purchasing Manager  
DATE: **March 29, 2024**  
SUBJECT: **Addendum #01**– P24-536: SURVEILLANCE SYSTEM UPGRADES

**This addendum has been issued to address the following Q&A as well as state a bid extension with an amended Bid Due Date/Bid Opening Date.**

**REVISED DUE DATE/BID OPENING DATE: Wednesday, March 24<sup>th</sup>, 2024 @ 11:00 EST**

**Q1: How many buildings that have cameras are on each site? Do you have prints?**

A1: Appendix A lists equipment and a general location or building. Appendix B shows proposed locations on graphical representations of the facilities. Prints of the facilities, as available, will be accessible after the bid has been awarded. To provide a proposed listing:

Water Service Center:

Main Building 7 Interior, 5 Exterior (including 1 on a remote pole)

Water Plant

Main Facility

PS4 1 Exterior (towards main gate), 1 Interior

CS2 1 Exterior

Plant 23 Exterior

Chem Feed 4 Interior

Holloway Dam 1 Exterior

Torrey Rd 1 Exterior, 1 Interior

Cedar St. 3 Exterior (1 on top of well), 1 Interior

West Side 1 Exterior, 2 Interior

Kearsley Dam 1 Exterior

Thread Dam 1 Exterior

**Q2: Are there network ports available in each of the buildings with cameras?**

A2: Each cost-center will have its own separate, independent camera network to be designed, procured, installed and programmed by the bid awardee in accordance with the bid specifications. There shall be no cloud storage.

**Q3: Are we to provide our own lift for this project or is a lift available for us to use?**

A3: Yes. Contractor will provide their own lift.

**Q4: As far as the existing cameras. Who is responsible to remove the existing equipment and cable?**

A4: The bid awardee.

**Q5: Is Asbestos in any of the buildings?**

A5: Not to our knowledge.



# City of Flint

## Department of Purchases & Supplies

---

**Q6: Is conduit required for the camera locations?**

A6: Conduit is required where cabling would be exposed and for underground raceways. Work shall meet NFPA 70 (NEC), 2023 edition. City of Flint Utilities' Standards are aluminum conduit and 3/4" minimum. PVC is acceptable for underground raceways provided there are metal sweeps and stub-ups. Surface raceway (e.g. wiremold) is acceptable where aesthetically appropriate and specifically approved.

**Q7: In the walk through it was mentioned that electrician and trenching costs are the contractors responsibility. Is that correct?**

A7: Yes.

**Q8: If so, then I would request more time for the bid due date to get an electrician and directional boring companies to look at the site.**

A8: The bid submission date shall be moved to Wednesday, April 24<sup>th</sup>, 2024. Coordination through Tim Donlan (810.691.9522) or John Florshinger (810.577.8909) shall be made to access sites. Directional boring is not recommended.

All other bidding terms, requirements, and conditions continue as indicated in the remaining original bid documents.

The Purchasing Manager, Lauren Rowley, is an officer for the City of Flint with respect to this RFP.

**In the submission of their proposal, Proposer must acknowledge receipt of this addendum. Proposer shall acknowledge this addendum by signing and returning one copy of this notice with their submission.**

Company Name: \_\_\_\_\_

Address: \_\_\_\_\_

City / State / Zip: \_\_\_\_\_

Telephone: \_\_\_\_\_ Fax: \_\_\_\_\_ Email: \_\_\_\_\_

Print Name: \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Thank you,

**Lauren Rowley, Purchasing Manager**