



# City of Flint

## Department of Purchases & Supplies

---

Sheldon A. Neeley

TO: All Proposers  
FROM: Lauren Rowley, Purchasing Manager  
DATE: **March 03, 2026**  
SUBJECT: **Addendum #01 – P26000527: UTAH DAM CLEANING**

**This addendum has been issued to address the following vendor Q&A:**

**Q1.) Please identify the extent of shore clearing that shall be included in the scope of work on the east and west sides of the dam bridge.**

**A1.)** Property marked plus an overhead aerial photo was attached.

**Q2.) Exhibit A of the proposal submittal requests “Detailed Summary of Pricing” - Will a uniform bid schedule of values be provided to break down and itemize the scope of work for all bidders?**

**A2.)** I'm trying, that's why I said just put down 40 tons for the quantity of debris removed so they can all bid the same amount but please add what any additional loads would cost if it runs over the projected 40 tons.

**Q3.) Is an estimate available for the approximate volume of debris removal and/or dredged spoils to be generated as part of the scope of work?**

**A3.)** 40 tons of wood and no dredge spoils.

**Q4.) During the pre-bid conference an existing sediment boom and turbidity curtain were present on the southwest end of the dam bridge adjacent to an apparent storm discharge pipe – will this remain in place during the course of the project and will successful bidder be responsible for maintaining condition during the project?**

**A4.)** This will remain in place and yes, the contractor is responsible for replacement if it is damaged.

**Q5.) Is any analytical data available from any prior sampling of built-up debris along the north side of the dam for waste characterization purposes?**

**A5.)** No

**Q6.) If waste characterization is within the scope of work for the successful bidder, please identify which analytes should be tested.**

**A6.)** It is not in the scope of work hopefully no analysis will be needed for light cleanup work.

**Q7.) It was noted during the pre-bid conference that the pedestrian walkways on the east and west side of the dam bridge are to remain open to the public throughout the course of the project – please confirm and advise/suggest suitable means and methods to safely perform shore clearing and debris removal directly adjacent to active walkways.**

**A7.)** The sidewalks and bike paths can be shut down during this project.

**Q8.) During the pre-bid conference it was noted that a low-elevation overhead line connecting a presumed former utility was still intact on the east side of the dam bridge, running north-south, tying into a utility pole on Utah Ave, will this overhead line be removed prior to the start of work or will it be the responsibility of the successful bidder to coordinate with the utility authority for verification of disconnection and removal?**

**A8.)** The CoF can coordinate the power shut down of both light poles during this project. The contractors will still be responsible to not damage the two light poles or they must replace them.



# City of Flint

## Department of Purchases & Supplies

---

**Q9.) What is the estimated timeline of the project including anticipated start date, expected duration, and any relevant deadlines?**

**A9.)** Since this is a critical bike path route I would like it done in a timely manner and by June 31, 2026

**Q10.) Can the field on the east side of the Utah Dam Bridge east of the Flint River Trail be utilized for staging equipment and/or a laydown area for dredged material to drain prior to loading and hauling offsite?**

**A10.)** Yes, but no dredged material.

**Q11.) Will removal, hauling and disposal of debris and/or dredged spoils be paid on a lump sum basis or on a unit rate basis, i.e. per ton or per cubic yard?**

**A11.)** Per ton, and payment will be when the job is done as long as it is 40 tons or less. If they hit 40 tons and there is more, they must let us know that there must be a change order so we know how much additional money is needed.

**Q12.) Will the successful bidder be responsible for obtaining EGLE and/or USACE permits to perform the debris removal within the Flint River?**

**A12.)** Yes, if needed.

**Q13.) Will City of Flint provide or require applications for permits for performing work in the Flint River?**

**A13.)** At this time, EGLE has not notified us that any permits are needed for this work.

**Q14.) Will the successful bidder be responsible for any sedimentation control measures to be implemented as part of the base scope of work?**

**A14.)** No (waiting on EGLE for clarification on this)

**Q14.) Will any third-party engineering or consulting firm be providing oversight during execution of the project?**

**A14.)** No.

**Q15.) Will the successful bidder be responsible for assembling and submitting a site-specific Health and Safety Plan (HASP) for this project to the City of Flint or their engineer for review and approval?**

**A15.)** Yes

**Q16.) How will City of Flint determine substantial completion of the project's intent to restore normal water flow, are historical stream gauge or flow meter records downstream of the project area available for reference?**

**A16.)** As long as all of the dry land has been cleared between the markings and all floating debris has been removed from the river the WTP Supervisor will approve the work has been done to the city's satisfaction.

**Q17.) Are any records available for recent bridge/dam inspection reports for the Utah Dam Bridge?**

**A17.)** Yes

**Q18.) Will we need to submit a bid bond with our bid proposal? If so, please clarify what percentage of the bid amount will be required.**

**A18.)** Yes, please include a 5% bid bond in your proposal submission.

**Q19.) The proposal package discusses bid submission by hard copy and electronic submission on bidnet direct. It is assumed that we can submit our proposal either electronically or hard copy. Please confirm.**

---



# City of Flint

## Department of Purchases & Supplies

---

**A19.)** Per the required specifications in the RFP, BOTH hard copies AND electronic must be submitted to be fully qualified. Electronic can be submitted directly through bidnet or to the specified email address in the RFP, and the Hard copies can either be hand-delivered to the receiving address or postal mailed.

**Q20.)** *Are there existing plans available for the dam structure? If so, please provide these for our review.*

**A20.)** Yes. Additional drawings are attached to this Addendum.

**Q21.)** *What is the depth of the water around the dam structure?*

**A21.)** Approximately 10-15 feet deep

**Q22.)** *What is the composition of the debris in the water – all that is visible at the surface of the water is the fallen trees? Is there silt or other debris? If there is silt or other debris, what is the anticipated depth of this material?*

**A22.)** Surface floating debris is the only thing that needs to be removed, no silt or dredging under this contract.

**Q23.)** *Please provide a quantity (or quantities for different types of materials) that we are to base our bid on? 40 tons of wood debris to be removed.*

**A23.)** The City will have a dumpster on site for debris/trash removal.

**Q24.)** *Please provide the exact limits of removals in the water that we are to perform (depth of removal, lateral limits along the dam, etc.)*

**A24.)** Anything that you can grab by hand floating on the surface.

**Q25.)** *Has the material been tested for contamination? If not, is the intent to have the contractor test the material to determine if it is contaminated? If the contractor is responsible for testing the material, how is this to be paid for this?*

**A25.)** No testing has been done, as far as I know there is no contamination so nothing will be tested.

**Q26.)** *Should the material be determined to be contaminated, please confirm that the City of Flint will be listed as the generator of this material.*

**A26.)** Yes

**Q27.)** *Please confirm that should the material be determined to be contaminated, the contractor will be paid for the handling and disposal of this material by change order as there is no way to assess if the material is contaminated prior to bid submission.*

**A27.)** Yes

**Q28.)** *At the site visit there was overhead wire in the work area around the dam that may have an impact on our work. Are these wires in service? If they are in service, will they be relocated or de-energized for our work?*

**A28.)** Yes they are in service, the city will have consumers energy de-energize while the work is being done, but the contractor is responsible to keep both light poles in tack and if any damage is done then the contractor must replace.

**Q29.)** *Are there any other known utilities in the area that could impact the work associated with this project?*

**A29.)** No.

**Q30.)** *Are there any restrictions associated with the bike trail that is crossing the existing dam structure? Can this trail be closed during our work?*

---



# City of Flint

## Department of Purchases & Supplies

---

A30.) Yes, the trail will be closed during this project.

**Q31.) At the pre-bid site walk-through, it was discussed that the City would like to have a portion of the riverbank around the dam structure to be cleared. This scope of work was not called out in the scope provided, is this work required? If so, please define the exact limits that we are to clear.**

A31.) Yes, we marked all of the areas that need cleaning.

**Q32.) The scope of work provided states "Must have marine-certified divers (if underwater work is expected). Is underwater work requiring divers expected? If so, please clarify the exact scope anticipated for the divers. It is suggested that you provide a line item on the bid form for a daily rate for divers.**

A32.) No, only surface floating debris will be removed.

**Q33.) There was no bid form provided in the proposal package, please provide a bid form, preferably with a breakdown of bid items and quantities.**

A33.) There was no specified bid form, and therefore a vendor can attach/submit any type or format of bid pricing as long as there is a grand total amount clearly indicated.

**Q34.) Are there anticipated start dates and completion dates for this work?**

A34.) Work is to be completed by June 30, 2026.

**Q35.) Is this project subject to EGLE permitting? If so, has the permit been applied for and approved? Please provide a copy of the permit, if available.**

A35.) At this time, EGLE has not stated that any permitting is required.

**Q36.) Are there any in water work restrictions that we need to be aware of related to fish spawning, muscles, etc?**

A36.) No

**Q37.) Is a turbidity curtain required to be installed during construction?**

A37.) No

**Q38.) Will the selected contractor need to provide a survey of river bottom to verify all debris/sediment/etc. has been removed?**

A38.) No

**Q39.) What are the limits for removal? IE 20ft upstream of the structure and to what depth is the contractor being asked to remove to? Will this include any material within the gate structure/guide slots?**

A39.) An aerial map shows the approximate area and the city has marked the property with paint and flags and anything inside the markings needs to be removed. Only floating material on top of the water needs to be removed, if you can grab it with your hand pull it out.

**Q40.) We assume that contamination testing will be required before sending the sediment and debris to a landfill? Will this be a pass through charge or is the city expecting the contractor to guesstimate this cost in their proposal?**

A40.) I do not anticipate any additional charges due to contamination but if this problem arises we will have to address it in a change order.



# City of Flint

## Department of Purchases & Supplies

---

**Q41.) Are there any known utilities in the area? If unknown, will the city provide this information prior to the bid submittal?**

**A41.)** Yes there is, the city will have consumers energy de-energize them while the work is being done, but the contractor still is responsible not to damage the two light poles or they will have to replace them.

**Q42.) After removing trees, Will stumps need to be sprayed? Or all vegetation within those limits?**

**A42.)** Trees that are cut down should be cut a maximum of one foot above ground.

**Q43.) If all vegetation is sprayed and removed will rip rap need to be installed to meet SEC measures?**

**A43.)** Do not spray vegetation and no SEC.

**Q44.) Is there any anticipated sediment removal or just the log jam and debris?**

**A44.)** Just log jam and debris to be removed

**Q45.) Can equipment be stored at water treatment plant for nights/weekend?**

**A45.)** Yes

All other bidding terms, requirements, and conditions continue as indicated in the remaining original bid documents.

The Purchasing Manager, Lauren Rowley, is an officer for the City of Flint with respect to this RFP.

**In the submission of their proposal, Proposer must acknowledge receipt of this addendum. Proposer shall acknowledge this addendum by signing and returning one copy of this notice with their submission.**

Company Name: \_\_\_\_\_

Address: \_\_\_\_\_

City / State / Zip: \_\_\_\_\_

Telephone: \_\_\_\_\_ Fax: \_\_\_\_\_ Email: \_\_\_\_\_


Print Name: \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Thank you,

**Lauren Rowley, Purchasing Manager**





APPROVED BY THE BOARD  
OF WATER COMMISSIONERS

WITNESSES

*Walter J. [Signature]*  
*Frank [Signature]*


*Walter J. [Signature]*  
*Walter J. [Signature]*

WATER SUPPLY DAM  
CITY OF FLINT, MICH.  
UTAH AVENUE  
GENERAL PLAN

AMBURSEY, DAN COMPANY  
ENGINEERS


Map No. 2225  
Scale 1" = 30'

2225  
1-10



PLAN

SECTION AA THROUGH BATH  
SHOWING DOWNSTREAM ELEVATION OF DAM



WATER SUPPLY DAM  
CITY OF FLINT, MICH.  
UTAH AVENUE  
PLAN AND ELEVATION

ANDRESEN DAM COMPANY  
ENGINEERS

Mr. V. E. ...  
Mr. J. H. ...  
Mr. ...  
Mr. ...



APPROVED BY THE BOARD  
OF WATER COMMISSIONERS

WITNESSES





*[Signature]*  
*[Signature]*

Drawn by	Checked by	Scale	Sheet No.
J. H. ...	V. E. ...	1" = 10'	20

PART ELEVATION



Note: Sheet Piling to be driven to least depth indicated by 30° and of such family as may be directed by the engineer.





APPROVED BY THE BOARDS  
OF WATER COMMISSIONERS  
WITNESS  
*[Signature]*  
*[Signature]*

WATER SUPPLY DAM  
CITY OF FLINT, MICH.  
UTAH AVENUE  
DETAILS OF DAM



AMBURSEY DAM COMPANY  
ENGINEERS  
NEW YORK  
DESIGNED BY  
CONSTRUCTION  
SUPERVISOR  
APPROVED BY  
CITY ENGINEER



STEEL SHOWN IN TOP OF FLOOR  
 PLAN OF FLOOR  
 STEEL SHOWN IN DOTTED ON FLOOR



PLAN AND ELEVATION OF PILE  
 Detail above floor slabs





APPROVED BY THE BOARD  
 OF WATER COMMISSIONERS  
 WITNESSES  
 \_\_\_\_\_  
 \_\_\_\_\_

WATER SUPPLY DAM  
 CITY OF FLINT, MICH  
 UTAH AVENUE  
 FLOOR PLAN


AMBUESEN DAM COMPANY  
 ENGINEERS and ARCHITECTS  
 242 S  
 10-12  
 15-10

FLOOR PLAN WEST ABUTMENT

FLOOR PLAN OF EAST ABUTMENT



SECTION THEU EAST ABUTMENT



APPROVED BY THE BOARD  
OF WATER COMMISSIONERS

WITNESSES  
 [Signature]  
 [Signature]


WATER SUPPLY DAM  
 CITY OF FLINT, MICH.  
 UTAH AVENUE  
 ABUTMENTS

PREPARED BY  
 ENGINEERS  
 2425  
 50











OPERATING PIER  
END ELEVATION-HAND RAIL





DOWNSTREAM HANDRAIL ON OPERATING PIER  
UPSTREAM END SIMILAR TO ABOVE




UPSTREAM HANDRAIL  
SHOWING GATE AT  
PIER

PLAN UPSTREAM RAILINGS  
WEST ABUTMENT




ELEVATION DOWNSTREAM RAILINGS  
WEST ABUTMENT




DETAIL OF LOWER  
PART OF RAILING  
AT CENTER PIER

DETAIL OF HAND RAIL  
FASTENING TO CONCRETE

PLAN DOWNSTREAM RAILINGS  
WEST ABUTMENT



DOWNSTREAM RAILINGS - WALKWAY



ELEVATION DOWNSTREAM RAILINGS - EAST ABUTMENT

WATER SUPPLY DAM  
CITY OF FLINT MICH  
17th AVENUE  
PLAN AND ELEVATION OF  
HAND RAILINGS

Prepared by  
Checked by  
Approved by  
Date







GRETCHEN WHITMER  
GOVERNOR

STATE OF MICHIGAN  
DEPARTMENT OF  
ENVIRONMENT, GREAT LAKES, AND ENERGY  
LANSING



PHILLIP ROOS  
DIRECTOR

January 30, 2024

VIA EMAIL

City of Flint  
1101 South Saginaw Street  
Suite N102  
Flint, Michigan 48505

Dear Sir or Madam:

SUBJECT: Utah Dam, Dam ID No. 1275; Genesee County

The enclosed Dam Safety Inspection Report and recommendations for the Utah Dam, Dam ID No. 1275, located in Genesee County was conducted by the Department of Environment, Great Lakes, and Energy (EGLE) at the request of the City of Flint, as provided by Section 31518(4) of Part 315, Dam Safety (Part 315), of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended (NREPA).

The purpose of this inspection was to evaluate the structural condition and hydraulic capacity of this dam, as required by Part 315 (Dam Safety), of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended.

The Utah Dam is in fair condition overall. However, the inspection report contains several recommended actions for monitoring and maintenance of deficiencies that do not currently pose a threat to the safety of the dam but should be addressed in the timeframes provided in the report. Specifically, the report recommends the following:

1. **Debris (Action: Maintenance):** Remove debris. Debris reduces the hydraulic capacity of the dam and can damage to adjacent structures due to the irregular flow patterns. Complete action as soon as possible.
  - a. Principal Spillway: Upstream
  - b. Principal Spillway: Gate 1
2. **Deteriorating Material (Action: Maintenance):** Remove the deteriorated concrete and install new concrete. Remove all deteriorated concrete, additional concrete may have to be removed to ensure the patch is a minimum of 3 inches thick. Roughen existing concrete surface to improve the patch bond. Install high strength concrete. If concrete deterioration is not repaired, it will continue to get worse and more expensive to repair. Complete action by December 31, 2024.
  - a. Principal Spillway: Abutment - Left Wall, Right Wall
3. **Trees (Action: Maintenance):** Flush cut and/or grind stump and remove debris from embankment. The stump should be cut a maximum of one foot above

ground. Establish appropriate vegetation if stump is being grinded. We do not recommend uprooting trees for removal. Tree roots can lead to piping failure by cultivating flow paths in the embankment especially when the tree dies. Trees can also cause extensive damage and/or failure when they are uprooted from a storm. Complete action by December 31, 2025.

- a. Principal Spillway: Abutment - Left Wall, Right Wall
4. **Brush (Action: Maintenance):** Remove brush by mowing and/or herbicide. Brush should be maintained a minimum of two times per year to prevent further establishment of woody vegetation. Brush negatively impacts a dam because the brush cover invites animal activity, impedes the visual inspections of the dam, and can kill vegetation that stabilizes the soil. Complete action by December 31, 2025.
    - a. Principal Spillway: Abutment - Left Wall, Right Wall
  5. All the gates should be removed because they no longer serve a purpose and could induce a dam failure by reducing the spillway capacity if a gate were to fall. Complete action by December 31, 2024.
  6. Review and update the Operation and Maintenance Plan (O&M Plan) regularly. Provide any updates to the Dam Safety Program.

If you have any questions or concerns regarding the inspection report or the recommendations, please contact me at 517-230-5866; ThelenM21@Michigan.gov; or EGLE, P.O. Box 30458, Lansing, Michigan 48909-7958.

Sincerely,



Mitchel Thelen, P.E., Regional Engineer  
Dam Safety Unit  
Water Resources Division

Enclosure

**DAM SAFETY INSPECTION REPORT  
UTAH DAM – DAM ID NO. 1275  
FLINT RIVER  
GENESEE COUNTY – SW 1/4 SECTION 32, T 08N, R 07E**



**OWNER(S)/OPERATOR(S):** City of Flint  
1101 South Saginaw Street  
Suite N102  
Flint, MI 48505

**HAZARD POTENTIAL  
CLASSIFICATION:** Low

**INSPECTION DATE:** September 22, 2023

**REPORT DATE:** January 30, 2024

**PREPARED AND INSPECTED BY:**

*Mitchel K Thelen*



Mitchel K. Thelen, P.E.  
Registration Number: 09306  
Dam Safety Unit  
Water Resources Division  
Department of Environment, Great Lakes, and  
Energy  
P.O. Box 30458  
Lansing, Michigan 48909  
517-280-5866

## INTRODUCTION

The purpose of this inspection was to evaluate the structural condition and hydraulic capacity of the Utah Dam, as required by Part 315 (Dam Safety), of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended. This inspection was conducted by the Department of Environment, Great Lakes, and Energy (EGLE) at the request of the City of Flint, as provided by Section 31518(4) of Part 315, Dam Safety (Part 315), of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended (NREPA).

The report is limited to a discussion of observations based on a visual investigation and review of any available previous inspection reports, plans, and data. This report should not be considered an in-depth engineering investigation. All references to “right” and “left” in this report are based on the observer facing downstream.

## CONCLUSIONS AND RECOMMENDATIONS

The Utah Dam is in fair condition. No existing dam safety deficiencies are recognized for normal loading conditions. Rare or extreme hydrologic and/or seismic events may result in a dam safety deficiency. Risk may be in the range to take further action.

The following recommended actions are listed by priority:

1. **Debris (Action: Maintenance):** Remove debris. Debris reduces the hydraulic capacity of the dam and can damage to adjacent structures due to the irregular flow patterns. Complete action as soon as possible.
  - a. Principal Spillway: Upstream
  - b. Principal Spillway: Gate 1
2. **Deteriorating Material (Action: Maintenance):** Remove the deteriorated concrete and install new concrete. Remove all deteriorated concrete, additional concrete may have to be removed to ensure the patch is a minimum of 3 inches thick. Roughen existing concrete surface to improve the patch bond. Install high strength concrete. If concrete deterioration is not repaired, it will continue to get worse and more expensive to repair. Complete action by December 31, 2024.
  - a. Principal Spillway: Abutment - Left Wall, Right Wall
3. **Trees (Action: Maintenance):** Flush cut and/or grind stump and remove debris from embankment. The stump should be cut a maximum of one foot above ground. Establish appropriate vegetation if stump is being grinded. We do not recommend uprooting trees for removal. Tree roots can lead to piping failure by cultivating flow paths in the embankment especially when the tree dies. Trees can also cause extensive damage and/or failure when they are uprooted from a storm. Complete action by December 31, 2025.
  - a. Principal Spillway: Abutment - Left Wall, Right Wall
4. **Brush (Action: Maintenance):** Remove brush by mowing and/or herbicide. Brush should be maintained a minimum of two times per year to prevent further establishment of woody vegetation. Brush negatively impacts a dam because the brush cover invites animal activity, impedes the visual inspections of the dam, and can kill vegetation that stabilizes the soil. Complete action by December 31, 2025.

- a. Principal Spillway: Abutment - Left Wall, Right Wall
- 5. All the gates should be removed because they no longer serve a purpose and could induce a dam failure by reducing the spillway capacity if a gate were to fall. Complete action by December 31, 2024.
- 6. Review and update the Operation and Maintenance Plan (O&M Plan) regularly. Provide any updates to the Dam Safety Program.

The dam's current low hazard potential rating remains appropriate.

**PROJECT INFORMATION**

According to our records, the Utah Dam was originally constructed in 1928 for the purpose of water supply. The dam no longer serves this purpose as all spillway gates have been abandoned in either partially to fully open positions for many years.

The Dam consists of the following parts:

<b>Principal Spillway</b>	
Spillway Type: Sluice Gate	Primary Material: Metal/Concrete
<b>Gate 1-6</b>	
Gate Type: Sluice	Width: 25'
Bay Material: Concrete	Height: 12'
Operation: Manual	Crest Elevation: 699
Gate Material: Metal	
<b>Abutment Maintenance Deck Pedestrian Deck</b>	

The Dam has the following measurements:

Structural Height (ft): 15.5	Normal Freeboard (ft): 15
Normal Head (ft): 2	Flood Freeboard (ft): -2.7
Hydraulic Height (ft): 17.7	Normal Impoundment (acre): 0

The dam was originally inspected by MDNR engineers in 1980. It has subsequently been inspected under Part 315 by Acres International Corporation in 1993; by Ayres, Lewis, Norris, & May, Inc. in 1998; by the Spicer Group in 2003; by Stantec Consulting Michigan, Inc. in 2008, and EGLE in 2017. Copies of these inspection reports are on file with the Dam Safety Program.

**SITE INVESTIGATION**

The following discussion of the dam's physical condition and appurtenances is based on observations and photographs obtained on the inspection date.

In addition to the specific findings listed below, it is important to continue good maintenance practices. These practices include regular inspection of the dam embankments and hydraulic structures for any deficiencies. Some of the more common issues that are found include growth of trees and brush, development of erosion areas, and animal burrows.

If woody vegetation is allowed to mature, it could develop an extensive root system. These root systems can lead to piping failure or if the brush and trees are uprooting in a storm, can cause extensive deterioration of the embankment. Embankments should be clear of woody vegetation and mowed 10 feet past the toe of the embankment. Similarly, animal burrows and surface erosion, can propagate into increased seepage and potentially piping failure, as well as lead to slope stability issues.

The following data was collected on the date of the inspection and includes deficiencies observed during the inspection and necessary actions for remediation of the observed deficiencies.

<b>Spillways</b>		
<b>Principal Spillway</b>		
What issues are present:	<i>Debris, Deteriorating Material, Trees, Brush</i>	
<b>Debris</b>		
Component:		<i>Gate 1</i>
Part:	<i>Upstream</i>	
Photo:	<i>3, 4</i>	<i>6</i>
Action Required:	<i>Maintenance</i>	
Describe action required:	<i>Remove debris.</i>	
<b>Deteriorating Material</b>		
Component:	<i>Abutment</i>	
Part:	<i>Left Wall, Right Wall</i>	
Photo:	<i>19,20,21,22</i>	
Material:	<i>Concrete</i>	
Action Required:	<i>Maintenance</i>	
Describe action required:	<i>Remove the deteriorated concrete and install new concrete.</i>	
<b>Trees</b>		
Component:	<i>Abutment</i>	
Part:	<i>Left Wall, Right Wall</i>	
Action Required:	<i>Maintenance</i>	
Describe action required:	<i>Flush cut and/or grind stump and remove debris from</i>	
<b>Brush</b>		
Component:	<i>Abutment</i>	
Part:	<i>Left Wall, Right Wall</i>	
Action Required:	<i>Maintenance</i>	
Describe action required:	<i>Remove brush by mowing and/or herbicide.</i>	

The above monitoring and maintenance items should be addressed in accordance with the Conclusions and Recommendations section of this report.


### **STRUCTURAL STABILITY**

Based upon observations during the inspection, there were no indicators of any conditions that represent an immediate threat to the dam's stability. No remedial action is required at this time.

## **HYDROLOGY AND HYDRAULICS**

The contributing drainage area to the Flint River at the Utah Dam is approximately 722 square miles. The design discharge for this low hazard potential dam is the 1 percent annual chance (100-year) flood discharge which is estimated to be 11,800 cubic feet per second (cfs). The Principal Spillway (Gate) has a maximum hydraulic capacity of approximately 8,630 cfs with no freeboard. The dam cannot pass the design flood inflow. The dam is overtopped by 3.9 feet during the design storm. However, the high tailwater conditions caused by the Hamilton Dam downstream prevent the dam from washing out when it overtops. Hamilton Dam is in the process of being removed. Once Hamilton Dam is removed the dam will be able to pass the design flow without overtopping.

Below are the calculated rating curves with and without the downstream effects of Hamilton Dam:



Hamilton Dam is in the process of being removed. Once Hamilton Dam is removed the dam will be able to pass the design flow without overtopping.

Hydraulic calculations and methodology used to make this determination are shown in Appendix C.

## **OPERATION AND MAINTENANCE**

Operation and maintenance (O&M) of the dam is performed by City of Flint. A written O&M Plan is not on record with the Dam Safety Program. The Dam Safety Program recommends creating an O&M Plan to ensure proper operation and maintenance of the Dam. The Dam Safety Program should be provided any future or current O&M Plans.

## **EMERGENCY ACTION PLAN**

An Emergency Action Plan (EAP) is not required under Part 315 for a low hazard potential dam. Our records indicate that an EAP has not been developed for the dam. **Every inspection cycle the owner shall review and update the dam's EAP and provide the updated EAP to the Dam Safety Program. An updated EAP has been overdue since December 31, 1905. Please provide this to the Dam Safety Unit as soon as possible.**


## **APPENDICES**

Appendix A - Location map,  
Appendix B - Inspection photographs  
Appendix C - Hydraulic calculations and methodology  
Appendix D - Hydrologic Data


UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275

Appendix A – Location Map


Utah Dam  
Dam ID No. 1,275  
Section 32  
T 08N  
R 07E  
Genesee County



Approximate Dam Location Aerial (1" = 0.7 miles)



Approximate Dam Location Topography, 5' Contours (1" = 0.7 miles)



**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**

**Appendix B – Inspection Photos**



**Photo #1: Principal Spillway Downstream.**




**Photo #2: Principal Spillway Downstream.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #3: Principal Spillway Upstream.  
Issue: Debris, Action: Maintenance.  
Severity: Moderate.**



**Photo #4: Principal Spillway Upstream.  
Issue: Debris, Action: Maintenance.  
Severity: Moderate.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #5: Principal Spillway.**



**Photo #6: Principal Spillway Gate 1.  
Issue: Debris, Action: Maintenance.  
Severity: Moderate.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #7: Principal Spillway Gate 1.**



**Photo #8: Principal Spillway Gate 1.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #9: Principal Spillway Gate 2.**



**Photo #10: Principal Spillway Gate 2.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #11: Principal Spillway Gate 2.**



**Photo #12: Principal Spillway Gate 2.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #13: Principal Spillway Gate 4.**



**Photo #14: Principal Spillway Gate 4.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #15: Principal Spillway Gate 6.**



**Photo #16: Principal Spillway Gate 6.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #17: Principal Spillway Gate 3.**



**Photo #18: Principal Spillway Gate 3.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #19: Principal Spillway Abutment Left Wall.  
Issue: Deteriorating Material, Action: Maintenance.  
Material: Concrete.**



**Photo #20: Principal Spillway Abutment Left Wall.  
Issue: Deteriorating Material, Action: Maintenance.  
Material: Concrete.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #21: Principal Spillway Abutment Right Wall.  
Issue: Deteriorating Material, Action: Maintenance.  
Material: Concrete.**



**Photo #22: Principal Spillway Abutment Right Wall.  
Issue: Deteriorating Material, Action: Maintenance.  
Material: Concrete.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**




**Photo #23: Principal Spillway Maintenance Deck.**



**Photo #24: Principal Spillway Maintenance Deck.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #25: Principal Spillway Maintenance Deck.**



**Photo #26: Principal Spillway Maintenance Deck.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #27: Principal Spillway Pedestrian Deck.**



**Photo #28: Principal Spillway Pedestrian Deck.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #29: Principal Spillway Pedestrian Deck.**



**Photo #30: Principal Spillway Pedestrian Deck.**

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**



**Photo #31: Impoundment.**




**Photo #32: 60" storm right side.**

**UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275**  
**Appendix C - Hydraulic Calculations and Methodology**

**Terminology**

Q: flow	W: water	F: flooding	n: normal condition	ot: orifice and tailwater condition
L: length	LS: loss	WP: wetter perimeter	t: tailwater condition	at: above weir and tailwater condition
E: energy	US: upstream	dN: normal depth	o: orifice condition	
A: area	DS: downstream	dC: critical depth	a: above weir condition	

**Flow Diagram**



**Calculations**

With Hamilton Dam  
 Rating Curve Table

id	Elev [ft]	Flow [cfs]
0	715.00	9271.07
2	715.20	9498.81
3	715.30	9610.50
4	715.40	9719.98
6	715.60	9943.58
7	715.70	10054.92
8	715.80	10169.36
9	715.90	10281.67
11	716.10	10510.97
12	716.20	10625.51
13	716.30	10742.41
15	716.50	10973.98
16	716.60	11090.32
17	716.70	11207.25
18	716.80	11324.72
20	717.00	11561.29
21	717.10	11680.38
22	717.20	11800.02
24	717.40	12040.90
25	717.50	12162.15

# UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

<b>Name:</b> Middle Gates	<b>Part Type:</b> Gate	<b>Flow Type:</b> Flow
<b>Count:</b> 4	<b>DS Part:</b> Outlet With Hamilton Dam	<b>DS Part 2:</b>
<b>Type:</b> Sluice	<b>Shape:</b> Rectangular	<b>Crest Type:</b> Flat
<b>Gate Height [ft]:</b> 12.5	<b>Gate Thickness [ft]:</b> 1	<b>Gate Material:</b> Metal
<b>Stem Width [ft]:</b> 0	<b>Top Elev [ft]:</b> 728	<b>Gate Percent Open [%]:</b> 80
<b>Elevation [ft]:</b> 699	<b>Width [ft]:</b> 25	<b>Contraction Type:</b> None
<b>Number of Piers:</b> 1	<b>Pier Type:</b> Rounded	<b>Depth [ft]:</b> 0.5
<b>Crest Width [ft]:</b> 5	<b>Front Slope [V1:H ]:</b> 0	<b>Back Slope [V1:H ]:</b> 0
<b>Crest Material:</b> Concrete	<b>Trash Rack:</b> None	

Id	Part							Gate Type	Orifice					
	Q [cfs]	E(US) [ft]	W(US) [ft]	L [ft]	E(DS) [ft]	W(DS) [ft]	VH(DS) [ft]		E [ft]	W [ft]	A [sft]	W(DS) [ft]	Q(t) [cfs]	L(t) [ft]
0	6180.71	715.00	715.00	0.01	714.99	713.52	0.32	DS	16.00	16.00	330.00	14.52	1545.18	0.01
2	6332.54	715.20	715.20	0.01	715.19	713.71	0.33	O	16.20	16.20	330.00	14.71	1583.14	0.01
3	6407.00	715.30	715.30	0.01	715.29	713.79	0.34	O	16.30	16.30	330.00	14.79	1601.75	0.01
4	6479.99	715.40	715.40	0.01	715.39	713.88	0.34	O	16.40	16.40	330.00	14.88	1620.00	0.01
6	6629.06	715.60	715.60	0.01	715.59	714.05	0.35	O	16.60	16.60	330.00	15.05	1657.26	0.01
7	6703.28	715.70	715.70	0.01	715.69	714.13	0.35	O	16.70	16.70	330.00	15.13	1675.82	0.01
8	6779.57	715.80	715.80	0.01	715.79	714.22	0.36	O	16.80	16.80	330.00	15.22	1694.89	0.01
9	6854.44	715.90	715.90	0.01	715.89	714.30	0.36	O	16.90	16.90	330.00	15.30	1713.61	0.01
11	7007.31	716.10	716.10	0.01	716.09	714.47	0.37	O	17.10	17.10	330.00	15.47	1751.83	0.01
12	7083.67	716.20	716.20	0.01	716.19	714.55	0.37	O	17.20	17.20	330.00	15.55	1770.92	0.01
13	7161.61	716.30	716.30	0.01	716.29	714.64	0.37	O	17.30	17.30	330.00	15.64	1790.40	0.01
15	7315.99	716.50	716.50	0.01	716.49	714.81	0.38	O	17.50	17.50	330.00	15.81	1829.00	0.01
16	7393.55	716.60	716.60	0.01	716.59	714.89	0.39	O	17.60	17.60	330.00	15.89	1848.39	0.01
17	7471.50	716.70	716.70	0.01	716.69	714.98	0.39	O	17.70	17.70	330.00	15.98	1867.88	0.01
18	7549.81	716.80	716.80	0.01	716.79	715.06	0.39	O	17.80	17.80	330.00	16.06	1887.45	0.01
20	7707.53	717.00	717.00	0.01	716.99	715.23	0.40	O	18.00	18.00	330.00	16.23	1926.88	0.01
21	7786.92	717.10	717.10	0.01	717.09	715.31	0.40	O	18.10	18.10	330.00	16.31	1946.73	0.01
22	7866.68	717.20	717.20	0.01	717.19	715.40	0.41	O	18.20	18.20	330.00	16.40	1966.67	0.01
24	8027.27	717.40	717.40	0.01	717.39	715.56	0.41	O	18.40	18.40	330.00	16.56	2006.82	0.01
25	8108.10	717.50	717.50	0.01	717.49	715.65	0.42	O	18.50	18.50	330.00	16.65	2027.02	0.01

<b>Name:</b> End Gates	<b>Part Type:</b> Gate	<b>Flow Type:</b> Flow
<b>Count:</b> 2	<b>DS Part:</b> Outlet With Hamilton Dam	<b>DS Part 2:</b>
<b>Type:</b> Sluice	<b>Shape:</b> Rectangular	<b>Crest Type:</b> Flat
<b>Gate Height [ft]:</b> 12.5	<b>Gate Thickness [ft]:</b> 1	<b>Gate Material:</b> Metal
<b>Stem Width [ft]:</b> 0	<b>Top Elev [ft]:</b> 728	<b>Gate Percent Open [%]:</b> 80
<b>Elevation [ft]:</b> 699	<b>Width [ft]:</b> 25	<b>Contraction Type:</b> None
<b>Number of Piers:</b> 0.5	<b>Pier Type:</b> Rounded	<b>Depth [ft]:</b> 0.5
<b>Crest Width [ft]:</b> 5	<b>Front Slope [V1:H ]:</b> 0	<b>Back Slope [V1:H ]:</b> 0
<b>Crest Material:</b> Concrete	<b>Trash Rack:</b> None	

Id	Part							Gate Type	Orifice					
	Q [cfs]	E(US) [ft]	W(US) [ft]	L [ft]	E(DS) [ft]	W(DS) [ft]	VH(DS) [ft]		E [ft]	W [ft]	A [sft]	W(DS) [ft]	Q(t) [cfs]	L(t) [ft]
0	3090.36	715.00	715.00	0.01	714.99	713.52	0.32	DS	16.00	16.00	330.00	14.52	1545.18	0.01
2	3166.27	715.20	715.20	0.01	715.19	713.71	0.33	O	16.20	16.20	330.00	14.71	1583.14	0.01
3	3203.50	715.30	715.30	0.01	715.29	713.79	0.34	O	16.30	16.30	330.00	14.79	1601.75	0.01
4	3239.99	715.40	715.40	0.01	715.39	713.88	0.34	O	16.40	16.40	330.00	14.88	1620.00	0.01
6	3314.53	715.60	715.60	0.01	715.59	714.05	0.35	O	16.60	16.60	330.00	15.05	1657.26	0.01
7	3351.64	715.70	715.70	0.01	715.69	714.13	0.35	O	16.70	16.70	330.00	15.13	1675.82	0.01
8	3389.79	715.80	715.80	0.01	715.79	714.22	0.36	O	16.80	16.80	330.00	15.22	1694.89	0.01
9	3427.22	715.90	715.90	0.01	715.89	714.30	0.36	O	16.90	16.90	330.00	15.30	1713.61	0.01
11	3503.66	716.10	716.10	0.01	716.09	714.47	0.37	O	17.10	17.10	330.00	15.47	1751.83	0.01
12	3541.84	716.20	716.20	0.01	716.19	714.55	0.37	O	17.20	17.20	330.00	15.55	1770.92	0.01
13	3580.80	716.30	716.30	0.01	716.29	714.64	0.37	O	17.30	17.30	330.00	15.64	1790.40	0.01
15	3657.99	716.50	716.50	0.01	716.49	714.81	0.38	O	17.50	17.50	330.00	15.81	1829.00	0.01
16	3696.77	716.60	716.60	0.01	716.59	714.89	0.39	O	17.60	17.60	330.00	15.89	1848.39	0.01
17	3735.75	716.70	716.70	0.01	716.69	714.98	0.39	O	17.70	17.70	330.00	15.98	1867.88	0.01
18	3774.91	716.80	716.80	0.01	716.79	715.06	0.39	O	17.80	17.80	330.00	16.06	1887.45	0.01
20	3853.76	717.00	717.00	0.01	716.99	715.23	0.40	O	18.00	18.00	330.00	16.23	1926.88	0.01
21	3893.46	717.10	717.10	0.01	717.09	715.31	0.40	O	18.10	18.10	330.00	16.31	1946.73	0.01
22	3933.34	717.20	717.20	0.01	717.19	715.40	0.41	O	18.20	18.20	330.00	16.40	1966.67	0.01
24	4013.63	717.40	717.40	0.01	717.39	715.56	0.41	O	18.40	18.40	330.00	16.56	2006.82	0.01
25	4054.05	717.50	717.50	0.01	717.49	715.65	0.42	O	18.50	18.50	330.00	16.65	2027.02	0.01

## UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

<b>Name:</b> Outlet With Hamilton Dam <b>Count:</b> 1 <b>Method:</b> GRV <b>N value:</b> 0.034 <b>Length [ft]:</b> 12000 <b>Right Side Slope [V/H]:</b> 1	<b>Part Type:</b> Channel <b>DS Part:</b> Hamilton Dam <b>Shape:</b> Trapezoidal <b>US Elevation [ft]:</b> 698.5 <b>Width [ft]:</b> 120	<b>Flow Type:</b> Flow <b>DS Part 2:</b> <b>Profile:</b> Line <b>DS Elevation [ft]:</b> 696 <b>Left Side Slope [V/H]:</b> 1
--	---	---

Id	Part								Channel				
	Q [cfs]	E(US) [ft]	W(US) [ft]	VH(US) [ft]	L [ft]	E(DS) [ft]	W(DS) [ft]	VH(DS) [ft]	W(US) [ft]	W(DS) [ft]	dN [ft]	dC [ft]	LS [ft]
0	9271.07	713.83	713.52	0.32	5.84	707.99	707.40	0.60	15.02	11.40	17.33	5.61	5.84
2	9498.81	714.02	713.70	0.33	5.91	708.11	707.49	0.61	15.20	11.49	17.57	5.70	5.91
3	9610.50	714.11	713.79	0.34	5.94	708.16	707.54	0.62	15.29	11.54	17.69	5.75	5.94
4	9719.98	714.19	713.87	0.34	5.98	708.21	707.58	0.63	15.37	11.58	17.81	5.79	5.98
6	9943.58	714.37	714.04	0.35	6.05	708.32	707.67	0.65	15.54	11.67	18.04	5.88	6.05
7	10054.92	714.46	714.13	0.35	6.09	708.37	707.71	0.66	15.63	11.71	18.16	5.92	6.09
8	10169.36	714.55	714.21	0.35	6.12	708.43	707.76	0.67	15.71	11.76	18.28	5.96	6.12
9	10281.67	714.63	714.30	0.36	6.16	708.48	707.80	0.68	15.80	11.80	18.39	6.01	6.16
11	10510.97	714.81	714.47	0.36	6.23	708.58	707.88	0.70	15.97	11.88	18.63	6.09	6.23
12	10625.51	714.90	714.55	0.37	6.26	708.64	707.93	0.71	16.05	11.93	18.75	6.14	6.26
13	10742.41	714.99	714.64	0.37	6.29	708.70	707.98	0.72	16.14	11.98	18.87	6.18	6.29
15	10973.98	715.16	714.80	0.38	6.36	708.80	708.06	0.74	16.30	12.06	19.10	6.27	6.36
16	11090.32	715.25	714.89	0.38	6.39	708.86	708.11	0.75	16.39	12.11	19.21	6.31	6.39
17	11207.25	715.33	714.97	0.39	6.42	708.91	708.16	0.76	16.47	12.16	19.33	6.36	6.42
18	11324.72	715.42	715.06	0.39	6.45	708.97	708.21	0.77	16.56	12.21	19.45	6.40	6.45
20	11561.29	715.60	715.22	0.40	6.51	709.09	708.30	0.78	16.72	12.30	19.68	6.49	6.51
21	11680.38	715.68	715.31	0.40	6.54	709.15	708.35	0.79	16.81	12.35	19.80	6.53	6.54
22	11800.02	715.77	715.39	0.40	6.57	709.20	708.40	0.80	16.89	12.40	19.91	6.57	6.57
24	12040.90	715.95	715.56	0.41	6.63	709.32	708.50	0.82	17.06	12.50	20.15	6.66	6.63
25	12162.15	716.03	715.64	0.42	6.65	709.38	708.55	0.83	17.14	12.55	20.26	6.71	6.65

<b>Name:</b> Hamilton Dam <b>Count:</b> 1 <b>Contraction Type:</b> None <b>Trash Rack:</b> None <b>Height [ft]:</b> 20 <b>Apron Elev [ft]:</b> 693	<b>Part Type:</b> Weir <b>DS Part:</b> <b>Number of Piers:</b> 0 <b>Elevation [ft]:</b> 700.8 <b>Depth [ft]:</b> 5 <b>Front Slope [V1:H]:</b> 0	<b>Flow Type:</b> Flow <b>Shape:</b> Ogee <b>Number of Bends:</b> 0 <b>Length [ft]:</b> 120 <b>Design Head [ft]:</b> 5 <b>Material:</b> Concrete
---	--	---

Id	Part						Weir					
	Q [cfs]	E(US) [ft]	W(US) [ft]	VH(US) [ft]	L [ft]	E(DS) [ft]	E [ft]	W [ft]	L(n) [ft]	C(n)	Q(n) [cs]	LS(n) [ft]
0	9271.19	708.00	707.40	0.60	0.67	707.32	7.20	6.60	120.00	4.10	9271.19	0.67
2	9498.86	708.10	707.49	0.61	0.66	707.45	7.30	6.69	120.00	4.11	9498.86	0.66
3	9610.69	708.16	707.54	0.62	0.66	707.51	7.36	6.74	120.00	4.11	9610.69	0.66
4	9720.25	708.21	707.58	0.63	0.65	707.56	7.41	6.78	120.00	4.12	9720.25	0.65
6	9962.09	708.32	707.67	0.65	0.63	707.69	7.52	6.87	120.00	4.13	9962.09	0.63
7	10055.05	708.37	707.71	0.66	0.63	707.74	7.57	6.91	120.00	4.13	10055.05	0.63
8	10169.55	708.43	707.76	0.67	0.63	707.80	7.63	6.96	120.00	4.13	10169.55	0.63
9	10281.96	708.47	707.79	0.68	0.62	707.86	7.67	6.99	120.00	4.14	10281.96	0.62
11	10511.26	708.58	707.88	0.70	0.60	707.97	7.78	7.08	120.00	4.15	10511.26	0.60
12	10625.69	708.64	707.93	0.71	0.60	708.03	7.84	7.13	120.00	4.15	10625.69	0.60
13	10742.60	708.69	707.98	0.72	0.60	708.09	7.89	7.18	120.00	4.15	10742.60	0.60
15	10974.16	708.80	708.06	0.74	0.59	708.21	8.00	7.26	120.00	4.16	10974.16	0.59
16	11090.51	708.86	708.11	0.75	0.59	708.27	8.06	7.31	120.00	4.16	11090.51	0.59
17	11207.43	708.91	708.16	0.76	0.58	708.33	8.11	7.36	120.00	4.16	11207.43	0.58
18	11324.90	708.97	708.21	0.77	0.58	708.39	8.17	7.41	120.00	4.16	11324.90	0.58
20	11561.47	709.09	708.30	0.78	0.58	708.51	8.29	7.50	120.00	4.16	11561.47	0.58
21	11680.56	709.14	708.35	0.79	0.58	708.57	8.34	7.55	120.00	4.16	11680.56	0.58
22	11800.20	709.20	708.40	0.80	0.58	708.63	8.40	7.60	120.00	4.16	11800.20	0.58
24	12041.08	709.32	708.50	0.82	0.57	708.75	8.52	7.70	120.00	4.16	12041.08	0.57
25	12162.33	709.38	708.55	0.83	0.57	708.80	8.58	7.75	120.00	4.16	12162.33	0.57

# UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

Hamilton Dam Removed

Rating Curve Table

id	Elev [ft]	Flow [cfs]
0	712.00	11025.99
2	712.20	11218.35
4	712.40	11342.65
5	712.50	11388.19
7	712.70	11472.73
8	712.80	11511.39
10	713.00	11580.95
11	713.10	11611.83
13	713.30	11668.07
14	713.40	11696.29
16	713.60	11745.75
18	713.80	11785.92
19	713.90	11806.77
21	714.10	11950.44
22	714.20	12074.79
24	714.40	12315.42
25	714.50	12437.40
27	714.70	12671.06
28	714.80	12788.16
30	715.00	13021.46

# UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

<b>Name:</b> Middle Gates <b>Count:</b> 4 <b>Type:</b> Sluice <b>Gate Height [ft]:</b> 12.5 <b>Stem Width [ft]:</b> 0 <b>Elevation [ft]:</b> 699 <b>Number of Piers:</b> 1 <b>Crest Width [ft]:</b> 5 <b>Crest Material:</b> Concrete	<b>Part Type:</b> Gate <b>DS Part:</b> Outlet <b>Shape:</b> Rectangular <b>Gate Thickness [ft]:</b> 1 <b>Top Elev [ft]:</b> 728 <b>Width [ft]:</b> 25 <b>Pier Type:</b> Rounded <b>Front Slope [V1:H_]:</b> 0 <b>Trash Rack:</b> None	<b>Flow Type:</b> Flow <b>DS Part 2:</b> <b>Crest Type:</b> Flat <b>Gate Material:</b> Metal <b>Gate Percent Open [%]:</b> 80 <b>Contraction Type:</b> None <b>Depth [ft]:</b> 0.5 <b>Back Slope [V1:H_]:</b> 0
---	---	--

Part								Gate			
Id	Q [cfs]	E(US) [ft]	W(US) [ft]	L [ft]	E(DS) [ft]	W(DS) [ft]	VH(DS) [ft]	Type	Weir%	Orifice%	dC [ft]
0	7337.81	712.00	712.00	2.70	709.30			W			5.51
2	7465.62	712.20	712.20	2.78	709.42			W			5.55
4	7548.14	712.40	712.40	2.86	709.54			W			5.63
5	7578.34	712.50	712.50	2.90	709.60			W			5.64
7	7634.38	712.70	712.70	2.98	709.72			W			5.67
8	7660.01	712.80	712.80	3.03	709.77			W			5.68
10	7706.08	713.00	713.00	3.12	709.88			W			5.70
11	7726.53	713.10	713.10	3.17	709.93			W			5.71
13	7763.74	713.30	713.30	3.26	710.04			W			5.73
14	7782.41	713.40	713.40	3.31	710.09			W			5.74
16	7815.11	713.60	713.60	3.41	710.19			W			5.75
18	7841.62	713.80	713.80	3.51	710.29			W			5.76
19	7855.39	713.90	713.90	3.57	710.33			W			5.77
21	7950.76	714.10	714.10	0.66	713.44			W			5.86
22	8033.38	714.20	714.20	0.66	713.54			W			5.89
24	8194.18	714.40	714.40	0.62	714.39	712.27	0.65	TDS	0.94	0.06	
25	8276.19	714.50	714.50	0.58	714.49	712.35	0.66	TDS	0.89	0.11	
27	8433.48	714.70	714.70	0.50	714.69	712.50	0.66	TDS	0.77	0.23	
28	8512.35	714.80	714.80	0.47	714.79	712.57	0.67	TDS	0.72	0.28	
30	8669.56	715.00	715.00	0.39	714.99	712.72	0.67	TDS	0.60	0.40	

Id	Weir											Orifice						
	E [ft]	W [ft]	L(n) [ft]	C(n)	Q(n) [cs]	LS(n) [ft]	W(DS) [ft]	C(t)	Q(t) [cfs]	L(t) [ft]	BtoS	E [ft]	W [ft]	A [sft]	W(DS) [ft]	Q(t) [cfs]	L(t) [ft]	
0	13.00	13.00	24.74	3.09	3580;35	1.42	12.40	0.57;0.98	2608;1283	0.57	0.4;0.6							
2	13.20	13.20	24.74	3.09	3662;41	1.41	12.54	0.6;0.98	2746;1330	0.58	0.36;0.64							
4	13.40	13.40	24.73	3.09	3745;52	1.40	12.62	0.63;0.98	2873;1371	0.59	0.32;0.68							
5	13.50	13.50	24.73	3.09	3787;59	1.39	12.65	0.63;0.97	2926;1393	0.60	0.3;0.7							
7	13.70	13.70	24.73	3.09	3871;75	1.38	12.71	0.65;0.97	3032;1439	0.61	0.26;0.74							
8	13.80	13.80	24.72	3.09	3913;84	1.38	12.74	0.66;0.97	3086;1462	0.62	0.24;0.76							
10	14.00	14.00	24.72	3.09	3997;102	1.37	12.78	0.67;0.96	3196;1507	0.64	0.2;0.8							
11	14.10	14.10	24.72	3.09	4040;113	1.36	12.80	0.68;0.96	3251;1529	0.65	0.18;0.82							
13	14.30	14.30	24.71	3.09	4126;134	1.35	12.84	0.69;0.96	3364;1575	0.67	0.14;0.86							
14	14.40	14.40	24.71	3.09	4169;146	1.35	12.86	0.7;0.96	3420;1599	0.68	0.12;0.88							
16	14.60	14.60	24.71	3.09	4255;170	1.34	12.89	0.72;0.95	3534;1646	0.69	0.08;0.92							
18	14.80	14.80	24.70	3.09	4342;196	1.33	12.92	0.73;0.95	3651;1694	0.71	0.04;0.96							
19	14.90	14.90	24.70	3.09	4386;211	1.32	12.93	0.74;0.95	3710;1718	0.72	0.02;0.98							
21	15.10	15.10	24.70	3.09	226.97	0.09	13.03	0.95	1760.72	0.73								
22	15.20	15.20	24.70	3.09	229.92	0.09	13.11	0.95	1778.43	0.73								
24	15.40	15.40	24.69	3.09	236.27	0.09	13.27	0.95	1814.59	0.73		15.40	15.40	330.00	13.27	2009.61	0.01	
25	15.50	15.50	24.69	3.09	240.59	0.09	13.35	0.95	1833.29	0.73		15.50	15.50	330.00	13.35	2030.82	0.01	
27	15.70	15.70	24.69	3.09	248.77	0.09	13.50	0.95	1870.11	0.72		15.70	15.70	330.00	13.50	2072.54	0.01	
28	15.80	15.80	24.68	3.09	252.97	0.09	13.57	0.95	1888.75	0.72		15.80	15.80	330.00	13.57	2093.68	0.01	
30	16.00	16.00	24.68	3.09	261.71	0.09	13.72	0.95	1926.19	0.72		16.00	16.00	330.00	13.72	2136.19	0.01	

# UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

<b>Name:</b> End Gates	<b>Part Type:</b> Gate	<b>Flow Type:</b> Flow
<b>Count:</b> 2	<b>DS Part:</b> Outlet	<b>DS Part 2:</b>
<b>Type:</b> Sluice	<b>Shape:</b> Rectangular	<b>Crest Type:</b> Flat
<b>Gate Height [ft]:</b> 12.5	<b>Gate Thickness [ft]:</b> 1	<b>Gate Material:</b> Metal
<b>Stem Width [ft]:</b> 0	<b>Top Elev [ft]:</b> 728	<b>Gate Percent Open [%]:</b> 80
<b>Elevation [ft]:</b> 699	<b>Width [ft]:</b> 25	<b>Contraction Type:</b> None
<b>Number of Piers:</b> 0.5	<b>Pier Type:</b> Rounded	<b>Depth [ft]:</b> 0.5
<b>Crest Width [ft]:</b> 5	<b>Front Slope [V1:H_]:</b> 0	<b>Back Slope [V1:H_]:</b> 0
<b>Crest Material:</b> Concrete	<b>Trash Rack:</b> None	

Id	Part							Gate			
	Q [cfs]	E(US) [ft]	W(US) [ft]	L [ft]	E(DS) [ft]	W(DS) [ft]	VH(DS) [ft]	Type	Weir%	Orifice%	dC [ft]
0	3688.18	712.00	712.00	2.70	709.30			W			5.53
2	3752.73	712.20	712.20	2.78	709.42			W			5.57
4	3794.52	712.40	712.40	2.86	709.54			W			5.65
5	3809.85	712.50	712.50	2.90	709.60			W			5.66
7	3838.34	712.70	712.70	2.98	709.72			W			5.69
8	3851.38	712.80	712.80	3.03	709.77			W			5.70
10	3874.86	713.00	713.00	3.12	709.88			W			5.72
11	3885.30	713.10	713.10	3.17	709.93			W			5.73
13	3904.33	713.30	713.30	3.26	710.04			W			5.75
14	3913.88	713.40	713.40	3.31	710.09			W			5.76
16	3930.64	713.60	713.60	3.41	710.19			W			5.77
18	3944.30	713.80	713.80	3.51	710.29			W			5.79
19	3951.38	713.90	713.90	3.57	710.33			W			5.80
21	3999.68	714.10	714.10	0.66	713.44			W			5.88
22	4041.41	714.20	714.20	0.66	713.54			W			5.92
24	4121.24	714.40	714.40	0.62	714.39	712.27	0.65	TDS	0.94	0.06	
25	4161.21	714.50	714.50	0.58	714.49	712.35	0.66	TDS	0.89	0.11	
27	4237.58	714.70	714.70	0.50	714.69	712.50	0.66	TDS	0.77	0.23	
28	4275.81	714.80	714.80	0.47	714.79	712.57	0.67	TDS	0.72	0.28	
30	4351.90	715.00	715.00	0.39	714.99	712.72	0.67	TDS	0.60	0.40	


Id	Weir										Orifice							
	E [ft]	W [ft]	L(n) [ft]	C(n)	Q(n) [cs]	LS(n) [ft]	W(DS) [ft]	C(t)	Q(t) [cfs]	L(t) [ft]	BtoS	E [ft]	W [ft]	A [sft]	W(DS) [ft]	Q(t) [cfs]	L(t) [ft]	
0	13.00	13.00	24.87	3.09	3599;36	1.42	12.40	0.57;0.98	2622;1290	0.57	0.4;0.6							
2	13.20	13.20	24.87	3.09	3682;42	1.41	12.54	0.6;0.98	2761;1337	0.58	0.36;0.64							
4	13.40	13.40	24.87	3.09	3765;53	1.40	12.62	0.63;0.98	2889;1378	0.59	0.32;0.68							
5	13.50	13.50	24.86	3.09	3807;60	1.39	12.65	0.63;0.97	2941;1401	0.60	0.3;0.7							
7	13.70	13.70	24.86	3.09	3892;76	1.38	12.71	0.65;0.97	3049;1447	0.61	0.26;0.74							
8	13.80	13.80	24.86	3.09	3935;84	1.38	12.74	0.66;0.97	3103;1470	0.62	0.24;0.76							
10	14.00	14.00	24.86	3.09	4020;103	1.37	12.78	0.67;0.96	3214;1515	0.64	0.2;0.8							
11	14.10	14.10	24.86	3.09	4063;113	1.36	12.80	0.68;0.96	3270;1538	0.65	0.18;0.82							
13	14.30	14.30	24.86	3.09	4149;135	1.35	12.84	0.69;0.96	3383;1584	0.67	0.14;0.86							
14	14.40	14.40	24.86	3.09	4193;146	1.35	12.86	0.7;0.96	3440;1608	0.68	0.12;0.88							
16	14.60	14.60	24.85	3.09	4280;171	1.34	12.89	0.72;0.95	3555;1656	0.69	0.08;0.92							
18	14.80	14.80	24.85	3.09	4368;198	1.33	12.92	0.73;0.95	3672;1704	0.71	0.04;0.96							
19	14.90	14.90	24.85	3.09	4412;212	1.32	12.93	0.74;0.95	3732;1728	0.72	0.02;0.98							
21	15.10	15.10	24.85	3.09	228.36	0.09	13.03	0.95	1771.48	0.73								
22	15.20	15.20	24.85	3.09	231.33	0.09	13.11	0.95	1789.37	0.73								
24	15.40	15.40	24.85	3.09	237.74	0.09	13.27	0.95	1825.91	0.73		15.40	15.40	330.00	13.27	2009.61	0.01	
25	15.50	15.50	24.84	3.09	242.10	0.09	13.35	0.95	1844.80	0.73		15.50	15.50	330.00	13.35	2030.82	0.01	
27	15.70	15.70	24.84	3.09	250.35	0.09	13.50	0.95	1882.00	0.72		15.70	15.70	330.00	13.50	2072.54	0.01	
28	15.80	15.80	24.84	3.09	254.59	0.09	13.57	0.95	1900.84	0.72		15.80	15.80	330.00	13.57	2093.68	0.01	
30	16.00	16.00	24.84	3.09	263.40	0.09	13.72	0.95	1938.67	0.72		16.00	16.00	330.00	13.72	2136.19	0.01	

# UTAH DAM - GENESEE COUNTY - DAM ID NO. 1275

Name: Outlet	Part Type: Channel	Flow Type: Flow
Count: 1	DS Part:	Method: Depth
Shape: Defined	Profile: Slope	N value: 0.034
US Elevation [ft]: 698.5	Slope [ft/ft]: 0.00088	Cross Section Name: Outlet

Id	Part						Channel					
	Q [cfs]	E(US) [ft]	W(US) [ft]	VH(US) [ft]	L [ft]	W(DS) [ft]	W(US) [ft]	A [sft]	WP [ft]	dN [ft]	dC [ft]	LS [ft]
0	11025.99	712.01	711.41	0.61	712.01	0.00	12.91	1767.14	168.07	12.91	7.87	712.01
2	11218.35	712.15	711.54	0.61	712.15	0.00	13.04	1788.26	168.69	13.04	7.96	712.15
4	11342.65	712.24	711.62	0.62	712.24	0.00	13.12	1801.74	169.08	13.12	8.02	712.24
5	11388.19	712.27	711.65	0.62	712.27	0.00	13.15	1806.70	169.22	13.15	8.04	712.27
7	11472.73	712.33	711.71	0.62	712.33	0.00	13.21	1815.89	169.49	13.21	8.08	712.33
8	11511.39	712.36	711.74	0.62	712.36	0.00	13.24	1820.07	169.61	13.24	8.10	712.36
10	11580.95	712.41	711.78	0.62	712.41	0.00	13.28	1827.59	169.82	13.28	8.13	712.41
11	11611.83	712.43	711.80	0.63	712.43	0.00	13.30	1830.92	169.92	13.30	8.14	712.43
13	11668.07	712.47	711.84	0.63	712.47	0.00	13.34	1837.00	170.10	13.34	8.17	712.47
14	11696.29	712.49	711.86	0.63	712.49	0.00	13.36	1840.05	170.19	13.36	8.18	712.49
16	11745.75	712.52	711.89	0.63	712.52	0.00	13.39	1845.39	170.34	13.39	8.21	712.52
18	11785.92	712.55	711.92	0.63	712.55	0.00	13.42	1849.71	170.47	13.42	8.22	712.55
19	11806.77	712.57	711.93	0.63	712.57	0.00	13.43	1851.95	170.53	13.43	8.23	712.57
21	11950.44	712.67	712.03	0.64	712.67	0.00	13.53	1867.41	170.98	13.53	8.30	712.67
22	12074.79	712.75	712.11	0.64	712.75	0.00	13.61	1880.76	171.37	13.61	8.36	712.75
24	12315.42	712.92	712.27	0.65	712.92	0.00	13.77	1906.37	172.09	13.77	8.47	712.92
25	12437.40	713.00	712.35	0.65	713.00	0.00	13.85	1919.35	172.46	13.85	8.52	713.00
27	12671.06	713.16	712.50	0.66	713.16	0.00	14.00	1944.08	173.17	14.00	8.63	713.16
28	12788.16	713.24	712.58	0.66	713.24	0.00	14.08	1956.40	173.52	14.08	8.68	713.24
30	13021.46	713.40	712.73	0.67	713.40	0.00	14.23	1980.94	174.22	14.23	8.79	713.40

## Defined Cross Sections



**Weir**

$$Q = CL_e H_e^{\frac{3}{2}}$$

Where:

$Q$  = discharge

$C$  = discharge coefficient

$L_e$  = effective length of crest

$H_e$  = energy head

*Design of Small Dams – Equation 3 (pg. 365)*

The energy loss through a weir is calculated with the equation shown below:

$$L_w = \frac{H_e * (\frac{2}{3} * \sqrt{2g} - C)^2}{2g}$$

Where:

$H_e$  = energy head

$C$  = discharge coefficient

**Weir Length**

The effective length that is calculated with the equation shown below:

$$L_e = L - (R_a + R_p + R_b) * H_e$$

Where:

$L$  = weir length

$R_a$  = entrance reduction factor

$R_p$  = pier reduction factor

$R_b$  = bend reduction factor

**Weir Entrance Factor**

The entrance factor is calculated with the equation shown below:

$$R_e = N * K_e$$

Where:

$N = 1$ : one side contracted and  $2$ : both sides contracted

$K_e$  = abutment contraction coefficient

	$K_e$
For square abutments with headwall at 90° to direction of flow	0.2
For round abutments with headwall at 90° to direction of flow, when $0.5H_e \geq r \geq 0.15H_e$	0.1
For round abutments with headwall not more than 45° to direction of flow and $r \gg 0.5H_e$	0

*Design of Small Dams (pg. 368)*

**Weir Pier Factor**

The pier factor is calculated with the equation shown below:

$$R_p = 2 * N * K_p$$

Where:


$N$  = number of piers

$K_p$  = abutment contraction coefficient

	$K_p$
For square-nosed piers with corners rounded on a radius equal to about 0.1 of the pier thickness	0.02
For round-nosed piers	0.01
For pointed-nose piers	0

*Design of Small Dams (pg. 271)*

Weir C Broad Vertical



Discharge Characteristics of Broad-Crested Weirs – Figure 3 (pg. 6): Coefficients of discharge for broad-crested weir with a vertical front slope and vertical back slope. C value is from the USGS test of Cornell curve.

Weir C Shallow

When the weir depth is shallow enough the flow behaves more like channel flow. A C value of 3.09 is used for this flow condition. The flow is considered shallow when  $H > 10P$ . A linear transition starts at  $H > 5P$  to smooth the curve and account for some uncertainty as to when the shallow flow condition starts.


Weir Submerged Short

The section of flow that is below the tailwater depth is calculates with the equation shown below:

$$Q = \int_0^d L_e * \sqrt{2g} * (\sqrt{H_e - y} - \sqrt{d - y} + \sqrt{VH_T}) * dy = C' * L_e * (H_e^{1.5} - d^{1.5} - (H_e - h)^{1.5} + (d - h)^{1.5} + 1.5 * \sqrt{VH_T} * h)$$


Where:

- $L_e$  = effective length of crest
- $C'$  = submerged weir coefficient
- $H_e$  = energy head
- $d$  = tailwater head
- $VH_T$  = tailwater velocity head



Ogee


An ogee crest is shaped for a designed head. The design head is used to determine the design C value. The shape of the ogee crest is what determine the design head. The image below shows how the design head determines the shape of the ogee crest. The design head that produce a shape closet to actual ogee weir shape is what is used in our calculation.



Design of Small Dams – Figure 9-22 (pg. 368): Ogee crest shape defined by compound curves


Ogee C

Figure 189, shown below, is used with the design head to find the design C value.



Design of Small Dams – Figure 9-23 (pg. 370): Discharge coefficients for vertical-faced ogee crest

When the head at the dam varies from the design head the ratio of the head to the design head is used in Figure 190, shown below, to determine the ratio of the C value to the design C value.



Design of Small Dams – Figure 9-24 (pg. 371): Coefficients of discharge for other than design head

**Weir C Shallow**

When the weir depth is shallow enough the flow behaves more like channel flow. A C value of 3.09 is used for this flow condition. The flow is considered shallow when  $H > 10P$ . A linear transition starts at  $H > 5P$  to smooth the curve and account for some uncertainty as to when the shallow flow condition starts.



**Weir Submerged Short**

The section of flow that is below the tailwater depth is calculates with the equation shown below:

$$Q = \int_0^d L_e * \sqrt{2g} * (\sqrt{H_e - y} - \sqrt{d - y} + \sqrt{VH_T}) * dy = C' * L_e * (H_e^{1.5} - d^{1.5} - (H_e - h)^{1.5} + (d - h)^{1.5} + 1.5 * \sqrt{VH_T} * h)$$

Where:

- $L_e$  = effective length of crest
- $C'$  = submerged weir coefficient
- $H_e$  = energy head
- $d$  = tailwater head
- $VH_T$  = tailwater velocity head




*Discharge Characteristics of Broad-Crested Weirs – (pg. 139) Fieley and Sterns coefficients for submerged weirs. Table was modified to be shown as percentage.*

**Orifice**

Orifice flow is calculated with the equation show below:

$$Q = \int_0^h C_d * w * \sqrt{2g(H_e - y)} * dy$$

$$Q = C_d * w * (H_e^{1.5} - (H_e - h)^{1.5})$$



Where:

- $C_d$  = Orifice Coefficient
- w = flow area width
- $H_e$  = energy head
- h = flow area height

The flow velocity is calculated with the equation shown below:

$$v = \sqrt{2gh}$$

Where:

- g = gravitational acceleration
- h = head of water

The table below shows the classification used to determine the orifice coefficient:

Description	$C_d$
Round Edge	0.98
Sharp Edge, Plate	0.62
Flat Edge, Short Tube	0.61
Flat Edge, Long Tube	0.82
Flat Edge, Short Tube, Re-entrant	0.54
Flat Edge, Long Tube, Re-entrant	0.72
Sharp Edge, Re-entrant	0.51

The energy loss though an orifice is calculated with the equation shown below:

$$L_o = (H_e * (1 - C_d))^2$$

**Orifice Submerged**


When the tailwater elevation is above the orifice elevation, the area that is below the tailwater elevations is calculated with the equation shown below:

$$Q = \int_0^d C_d * w * \sqrt{2g} * (\sqrt{H_e - y} - \sqrt{d - y} + \sqrt{VH_T}) * dy$$

$$Q = C_d * w * (H_e^{1.5} - d^{1.5} - (H_e - d)^{1.5} + 1.5 * \sqrt{VH_T} * d)$$


Where:

- d = tailwater head
- $VH_T$  = tailwater velocity head
- $C_d$  = Orifice Coefficient
- w = flow area width
- $H_e$  = energy head



### Gate

Gates are calculated with three different flow types as depicted in the image below.



To determine orifice flow vs weir flow the critical depth is calculated for the flow and if the critical depth is within 25 percent of the bottom of gate elevation both weir and orifice/over top flow are calculated and a linear interpolation is used with the two flows. Both are calculated and interpolated within this range to create a smoother rating curve and acknowledge that when weir flow will transition to orifice flow is uncertain.

### Gate Submerged

Orifice flow can also be triggered by downstream conditions. Once the downstream elevation is above the bottom of the gate, a linear transition from weir flow to orifice flow in the range of  $G_{elev} < DS_{elev} < 1.1G_{elev}$ . This transition is to smooth the curve and account for uncertainty to when the flow transition from weir to orifice.

### Channel

#### Channel Depth

If the slope of the channel is horizontal or adverse the critical depth is used for the flow depth. Otherwise, the normal depth is used for the flow depth. The water elevation and energy elevation are determined from the flow depth. The upstream and downstream sides will have the same flow depth.

#### Channel Profile

The flow depth in the channel will vary as calculated using the gradually varied flow (GRV) direct step method described below. If the channel slope is steep or critical the GRV starts at the upstream end. If the channel slope is mild, horizontal, or adverse the GRV starts at the downstream end.

### Gradually Varied Flow

The water depth is calculated with equation shown below

$$\frac{dy}{dx} = \frac{S_o - S_f}{1 - Fr^2}$$

Where:

$S_o$  = bottom slope, positive in the downward direction

$S_f$  = Friction slope, positive in the downward direction

y = water depth, measured from culvert bottom to water surface

x = longitudinal distance, measured along the culvert bottom

Fr = Froude number

The friction slope is calculated with equation shown below:

$$S_f = \left( \frac{n * Q}{1.49 * A * R^{\frac{2}{3}}} \right)^2$$

Where:

n = manning's roughness coefficient

Q = flow

A = flow area

R = hydraulic radius

The Froude number is calculated with the equation shown below:

$$Fr = \frac{T * Q^2}{32.17 * A^3}$$

Where:

Q = flow

A = flow area

T = top width of water surface

The direct step method, as shown below, is used to determine the water profile. The friction slope is calculated a step is taken then a second friction slope is calculated, and the average friction slope is used to determine the change in water depth.

$$S_{f1} = \left( \frac{n * Q}{1.49 * A_1 * R_1^{\frac{2}{3}}} \right)^2$$

$$\frac{dy_1}{dx} = \frac{S_o - S_{f1}}{1 - Fr^2}$$

$$y_2 = y_1 + \frac{dy_1}{dx} * dx$$

$$S_{f2} = \left( \frac{n * Q}{1.49 * A_2 * R_2^{\frac{2}{3}}} \right)^2$$

$$\bar{S}_f = \frac{S_{f1} + S_{f2}}{2}$$

$$\frac{dy}{dx} = \frac{S_o - \bar{S}_f}{1 - Fr^2}$$

The dx is reduced when the change in depth is large or change in profile slope is large and dx is increased when the change of depth is small and change in profile slope is small.

The water surface profile can be calculated from downstream going upstream (backwater calculations) or from upstream going downstream (front water calculations). The direction depends on the classification of the water surface profile (hydraulic slope and type of curve). A backwater calculation is used for mild, critical, adverse, and horizontal slopes a backwater calculation beginning at the downstream boundary. A Front water calculation is used for steep slopes, beginning at the upstream boundary.

### Routing

The flow is determined by calculating the flow from upstream to downstream. Then the flow is calculated from downstream to upstream. If the tailwater conditions are not within 0.01 of a foot, the same process is repeated until the tailwater conditions converge. The routing ensures that the conservation of mass and energy are validated.

When a part as upstream parts, the cumulative flows and the proportional energy heads are how the final flow and energy head is used for the calculation. The part is calculated iteratively until the flow matches the flow from the upstream parts. If the energy head required for the flow is more than the energy head from the upstream parts. The tailwater conditions will increase and the upstream parts will be recalculated until the energy is conserved.

**UTAH DAM  
GENESEE COUNTY  
DAM ID NO. 1275**

**Appendix D – Hydrologic Data**

We have processed the discharge request submitted by email on October 18, 2023 (Process No. 20230546), as follows:

Flint River at Utah Dam, Dam ID 1275, Section 32, T8N, R7E, City of Flint, Genesee County, has a total drainage area of 732 square miles and a contributing drainage area of 723 square miles. The design discharge for this dam is the 1% chance (100-year) flood. The 1% chance peak flow is estimated to be 11800 cubic feet per second. (Watershed Basin No. 32B Flint).

These estimates should be confirmed by our office if an application is not submitted within one year. If you have any questions concerning the discharge estimates, please contact Ms. Susan Greiner, Hydrologic Studies and Floodplain Management Unit, at 517-927-3838, or by email at: [GreinerS@michigan.gov](mailto:GreinerS@michigan.gov).

-----Original Message-----

From: EGLE-Automated <[EGLE-Automated@michigan.gov](mailto:EGLE-Automated@michigan.gov)>  
Sent: Wednesday, October 18, 2023 12:42 PM  
To: EGLE-wrd-qreq <[EGLE-wrd-qreq@michigan.gov](mailto:EGLE-wrd-qreq@michigan.gov)>  
Subject: Flood or Low Flow Discharge Request

Requestor: Mitchel  
Company: EGLE  
Address: 525 W. Allegan  
City/State: Lansing  
ZIP Code: 48933  
Phone: 5172305866  
Date: 10/18/2023  
1 percent  
Contact Agency:  
Contact Person:  
Watercourse: Flint River  
Local Name:  
County: Genesee  
City/Township: ?  
Section: 32  
Town: 08N  
Range: 07E  
Location: Utah Dam #1275  
FFR1: Dam  
Email: [ThelenM21@michigan.gov](mailto:ThelenM21@michigan.gov)