

Category #	Category Desc	Pay Item	Description	Quantity	Units
1	Roadwork	1027060	Reimbursed Permit Fees	1200	Dlr
1	Roadwork	1100001	Mobilization, Max	1	LSUM
1	Roadwork	2020004	Tree, Rem, 6 inch to 18 inch	2	Ea
1	Roadwork	2040035	Guardrail, Rem	90	Ft
1	Roadwork	2040055	Sidewalk, Rem	263	Syd
1	Roadwork	2047011	Pavt, Rem, Modified	1270	Syd
1	Roadwork	2050010	Embankment, CIP	215	Cyd
1	Roadwork	2050016	Excavation, Earth	893	Cyd
1	Roadwork	2080020	Erosion Control, Inlet Protection, Fabric Drop	2	Ea
1	Roadwork	2080036	Erosion Control, Silt Fence	420	Ft
1	Roadwork	3010002	Subbase, CIP	469	Cyd
1	Roadwork	3020010	Aggregate Base, 4 inch	152	Syd
1	Roadwork	3020016	Aggregate Base, 6 inch	1044	Syd
1	Roadwork	3027011	Aggregate Base, 22 inch	275	Syd
1	Roadwork	4030005	Dr Structure Cover, Adj, Case 1	8	Ea
1	Roadwork	4030010	Dr Structure Cover, Type B	4	Ea
1	Roadwork	4030050	Dr Structure Cover, Type K	2	Ea
1	Roadwork	4030065	Dr Structure Cover, Type Q	2	Ea
1	Roadwork	4030280	Dr Structure, Adj, Add Depth	5	Ft
1	Roadwork	4040033	Underdrain, Fdn, 6 inch	186	Ft
1	Roadwork	4040061	Underdrain, Subbase, 4 inch	496	Ft
1	Roadwork	4040093	Underdrain Outlet, 6 inch	30	Ft
1	Roadwork	4040113	Underdrain, Outlet Ending, 6 inch	3	Ea
1	Roadwork	5010061	HMA Approach	402	Ton
1	Roadwork	8020038	Curb and Gutter, Conc, Det F4	380	Ft
1	Roadwork	8027001	Curb and Gutter, Bridge Approach, Det 5, Modified	55	Ft
1	Roadwork	8030010	Detectable Warning Surface	24	Ft
1	Roadwork	8030030	Curb Ramp Opening, Conc	66	Ft
1	Roadwork	8030044	Sidewalk, Conc, 4 inch	2270	Sft
1	Roadwork	8032001	Curb Ramp, Conc, 4 inch	475	Sft
1	Roadwork	8070044	Guardrail Approach Terminal, Type 2M	1	Ea
1	Roadwork	8070080	Guardrail Reflector	5	Ea

1 Roadwork	8070130 Guardrail Anch, Bridge, Det M1	1 Ea
1 Roadwork	8072179 Guardrail, Type MGS-8, 72 inch Post	25 Ft
1 Roadwork	8080007 Fence, Protective	200 Ft
1 Roadwork	8100371 Post, Steel, 3 pound	45 Ft
1 Roadwork	8100402 Sign, Type III, Erect, Salv	1 Ea
1 Roadwork	8100403 Sign, Type III, Rem	5 Ea
1 Roadwork	8100405 Sign, Type IIIB	17 Sft
1 Roadwork	8102010 Ground Mtd Sign Support, Rem	5 Ea
1 Roadwork	8110091 Pavt Mrkg, Polyurea, 4 inch, White	827 Ft
1 Roadwork	8110092 Pavt Mrkg, Polyurea, 4 inch, Yellow	806 Ft
1 Roadwork	8110093 Pavt Mrkg, Polyurea, 6 inch, Crosswalk	128 Ft
1 Roadwork	8110105 Pavt Mrkg, Polyurea, Bike, Small Sym	3 Ea
1 Roadwork	8110114 Pavt Mrkg, Polyurea, 24 inch, Stop Bar	32 Ft
1 Roadwork	8110307 Rem Curing Compound, for Longit Mrkg, 4 inch	889 Ft
1 Roadwork	8110308 Rem Curing Compound, for Longit Mrkg, 6 inch	34 Ft
1 Roadwork	8110321 Rem Curing Compound, for Spec Mrkg	214 Sft
1 Roadwork	8110405 Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	2 Ea
1 Roadwork	8112170 Pavt Mrkg, Polyurea, Bike Thru Arrow Sym	3 Ea
1 Roadwork	8120012 Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	16 Ea
1 Roadwork	8120013 Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	16 Ea
1 Roadwork	8120026 Pedestrian Type II Barricade, Temp	17 Ea
1 Roadwork	8120035 Channelizing Device, 42 inch, Fluorescent, Furn	50 Ea
1 Roadwork	8120036 Channelizing Device, 42 inch, Fluorescent, Oper	50 Ea
1 Roadwork	8120140 Lighted Arrow, Type C, Furn	2 Ea
1 Roadwork	8120141 Lighted Arrow, Type C, Oper	2 Ea
1 Roadwork	8120170 Minor Traf Devices	1 LSUM
1 Roadwork	8120310 Sign Cover	54 Ea
1 Roadwork	8120350 Sign, Type B, Temp, Prismatic, Furn	750 Sft
1 Roadwork	8120351 Sign, Type B, Temp, Prismatic, Oper	750 Sft
1 Roadwork	8120352 Sign, Type B, Temp, Prismatic, Spec, Furn	236 Sft
1 Roadwork	8120353 Sign, Type B, Temp, Prismatic, Spec, Oper	236 Sft
1 Roadwork	8120370 Traf Regulator Control	1 LSUM
1 Roadwork	8167011 Slope Restoration, Modified	229 Syd

1 Roadwork	8200458 TS Face, Bag	8 Ea
1 Roadwork	8230432 Gate Box, Adj, Case 2	1 Ea
2 Structure Work	2040001 Asbestos Materials, Rem and Disposal	5000 Dlr
2 Structure Work	2040061 Structures, Rem Portions	1 LSUM
2 Structure Work	2060002 Backfill, Structure, CIP	264 Cyd
2 Structure Work	2060010 Excavation, Fdn	264 Cyd
2 Structure Work	7060001 Bridge Ltg, Furn and Rem	1 LSUM
2 Structure Work	7060002 Bridge Ltg, Oper and Maintain	287 Cyd
2 Structure Work	7060050 Expansion Joint Device	128 Ft
2 Structure Work	7060051 Expansion Joint Device, Cover Plate	24 Ft
2 Structure Work	7060060 False Decking	13013 Sft
2 Structure Work	7060092 Reinforcement, Steel, Epoxy Coated	9363 Lb
2 Structure Work	7060092 Reinforcement, Steel, Epoxy Coated	73761 Lb
2 Structure Work	7060100 Substructure Conc	118 Cyd
2 Structure Work	7060110 Superstructure Conc	72 Cyd
2 Structure Work	7060111 Superstructure Conc, Form, Finish, and Cure (SN 2841)	1 LSUM
2 Structure Work	7060112 Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 2841)	1 LSUM
2 Structure Work	7060113 Superstructure Conc, Night Casting	287 Cyd
2 Structure Work	7060220 Sealing Localized Cracks (SN 2841)	1 LSUM
2 Structure Work	7067050 Structure Name Plate	1 Ea
2 Structure Work	7070050 Structural Steel, Mixed, Erect	15178 Lb
2 Structure Work	7070070 Structural Steel, Rolled Shape, Erect	209268 Lb
2 Structure Work	7077008 Bearing, Elastomeric, 1 1/8 inch	11520 Sin
2 Structure Work	7077030 Structural Steel, Rolled Shape, Furn and Fab, Galvanized	209268 Lb
2 Structure Work	7077030 Structural Steel, Mixed, Furn and Fab, Galvanized	15178 Lb
2 Structure Work	7077051 Shear Developers, Galvanized (SN 2841)	1 LSUM
2 Structure Work	7100001 Joint Waterproofing	1055 Sft
2 Structure Work	7107010 Silane Treatment	2894 Sft
2 Structure Work	7110010 Bridge Railing, 4 Tube	239 Ft
2 Structure Work	7120033 Adhesive Anchoring of Vertical Bar, 5/8 inch	624 Ea
2 Structure Work	7160001 Field Repr of Damaged Coating (SN 2841)	1 LSUM
2 Structure Work	8040000 Sealing Localized Conc Barrier Cracks (SN 2841)	1 LSUM