

CITY OF FLINT

Department of Purchases & Supplies

Dr. Karen Weaver Mayor Derrick F. Jones Purchasing Manager

INVITATION TO BID

OWNER:

THE CITY OF FLINT DEPARTMENT OF PURCHASES AND SUPPLIES 1101 S. SAGINAW ST., Room 203 FLINT, MI 48502

Proposal No. 17-564

SCOPE OF WORK:

The City of Flint, Department of Purchases & Supplies, is soliciting sealed proposals for providing:

2017 REPLACEMENT OF WATER SERVICE LINES (ZONES 1-9)

per the attached requirements.

If your firm is interested in providing the requested services, please submit 1 original, 1 copy, and 1 unbound copy of your detailed proposal to the City of Flint, Department of Purchases and Supplies, 1101 S. Saginaw St., Room 203, Flint, MI, 48502, by <u>Friday, March 3, 2017 @ 10:00 AM EST</u>). Please note: all proposals received after 10:00 AM (EST) will not be considered. Faxed proposals into the Purchasing Department are not accepted.

A bid guaranty or a cashier's check for \$75,000 for each zone bid (\$750,000 maximum), must be submitted with the bid. Please note: cashier' check must be payable to Treasurer, City of Flint. Contractors may bid on as many zones as they choose, however, the bid bond requirement will be based on the number of zones the Contract has placed in the section that poses the question of, "...what is the maximum number of zones that you are willing to accept and capable of completing in conformance with the requirements of this document?" If the contractor states one (1), then the bid bond requirement is \$75,000 (maximum number of maximum zones willing to accept 1 X \$75,000). Likewise if the contractor states ten (10), the bid bond requirement is \$750,000.

All additional bid documents, requirements, addendums, specifications and plans/drawings (if utilized) are available on the Purchasing page of the City of Flint's web site at www.cityofflint.com/purchasing under "open bids" and the specific bid or proposal number assigned to this notice.

INSTRUCTIONS TO VENDORS

- 1) PRE-BID INFORMATION AND QUESTIONS: Each proposal that is timely received will be evaluated on its merit and completeness of all requested information. In preparing proposals, Bidders are advised to rely only upon the contents of this Request for Proposal (RFP) and accompanying documents and any written clarifications or addenda issued by the City of Flint. If a Bidder finds a discrepancy, error or omission in the RFP package, or requires any written addendum thereto, the Bidder is requested to notify the Purchasing contact noted on the cover of this RFP, so that written clarification may be sent to all prospective Bidders. THE CITY OF FLINT IS NOT RESPONSIBLE FOR ANY ORAL INSTRUCTIONS.
- 2) RFP MODIFICATIONS: The City of Flint has the right to correct, modify or cancel the RFP, in whole or in part, or to reject any proposal, in whole or in part, within the discretion of the City of Flint, or their designee. If any such changes are made, all known recipients of the RFP will be sent a copy of such changes. If any changes are made to this RFP document by any party other than the City of Flint, the original document in the City of Flint's files takes precedence.

3) BID SUBMISSION:

- a) The Bidder must include the following items, or the bid may be deemed non-responsive: i.e. All forms contained in this RFP, fully completed.
- b) Proposal must be submitted to the Purchasing Department, City of Flint, 1101 S. Saginaw Street -Room 203, Flint, Michigan 48502 by the date and time indicated as the deadline. The Purchasing Department's time stamp will determine the official receipt time. It is each Bidder's responsibility to insure that its bid is time stamped by the Purchasing Department by the deadline. This responsibility rests entirely with the Bidder, regardless of delays resulting from postal handling or for any other reasons. Bids will be accepted at any time during the normal course of business only, said hours being 8:00 a.m. to 5:00 p.m. Local Time, Monday through Friday, legal holidays as exception.
- c) Proposals must be enclosed in a sealed, non-transparent envelope, box or package, and clearly marked on the outside with the following: RFP Title, RFP Number, Deadline and Bidder's name.
- d) Submission of a proposal establishes a conclusive presumption that the Bidder is thoroughly familiar with the Request for Proposal (RFP), and that the Bidder understands and agrees to abide by each and all of the stipulations and requirements contained therein.
- e) All prices and notations must be typed or printed in ink. No erasures are permitted. Mistakes may be crossed out and corrections must be initialed in ink by the person(s) signing the bid.
- f) Proposals sent by email, facsimile or other electronic means will not be considered unless specifically authorized in this RFP.
- g) All costs incurred in the preparation and presentation of the proposal are the Bidder's sole responsibility; no pre-bid costs will be reimbursed to any Bidder. All documentation submitted with the proposal will become the property of the City of Flint.
- h) Proposal must be held firm for a minimum of 120 days.
- i) Term Contract and/or all other procurement documents shall be effective until completed to the satisfaction of the City of Flint. The City of Flint reserves the right to cancel or not renew all or any part of the procurement agreement/contract at any time.

- 4) EXCEPTIONS: Bidder shall clearly identify any proposed deviations from the Terms or Scope in the Request for Proposal. Each exception must be clearly defined and referenced to the proper paragraph in this RFP. The exception shall include, at a minimum, the Bidder's proposed substitute language and opinion as to why the suggested substitution will provide equivalent or better service and performance. If no exceptions are noted in the Bidder's proposal, the City of Flint will assume complete conformance with this specification and the successful Bidder will be required to perform accordingly. Proposals not meeting all requirements may be rejected.
- 5) **DUPLICATE PROPOSALS:** No more than one (1) proposal from any Bidder, including its subsidiaries, affiliated companies and franchises will be considered by the City of Flint. In the event multiple proposals are submitted in violation of this provision, the City will have the right to determine which bid will be considered, or at its sole option, reject all such multiple proposal.
- 6) **WITHDRAWAL:** Proposals may only be withdrawn by written notice prior to the date and time set for the opening of bids. No proposal may be withdrawn after the deadline for submission.
- 7) REJECTION/GOOD STANDING: The City of Flint reserves the right to reject any or all proposals, or to accept or reject any proposal in part, and to waive any minor informality or irregularity in bids received if it is determined by the City of Flint, or their designee, that the best interest of the City will be served by doing so. No proposal will be considered from any person, firm or corporation in arrears or in default to the City on any contract, debt, taxes or other obligation, or if the Bidder is debarred by the City of Flint from consideration for a contract award.
- 8) **PROCUREMENT POLICY:** Procurement for the City of Flint will be handled in a manner providing fair opportunity to all businesses. This will be accomplished without abrogation or sacrifice of quality and as determined to be in the best interest of the City. The City of Flint and their officials have the vested authority to execute a contract, subject to City Council and Mayoral approval where required.
- 9) BID SIGNATURES: Proposals must be signed by an authorized official of the Bidder. Each signature represents binding commitment upon the Bidder to provide the goods and/or services offered to the City of Flint if the Bidder is determined to be the lowest Responsive and Responsible Bidder.
- 10) CONTRACT AWARD/SPLIT AWARDS: This contract will be awarded to the lowest responsive, responsible Bidder for each of ten (10) zones based on the criteria set in #44 below. A bidder may be awarded zero, one, multiple, or all zones. Therefore, award will be made to between zero and ten different vendors. The Bidder to whom the award is made will be notified at the earliest possible date. Tentative acceptance of the bid, intent to recommend award of a contract, and actual award of the contract will be provided by written notice sent to the Bidder at the address designated in the bid if a separate Agreement is required to be executed. After a final award of the Agreement by the City of Flint, the Contractor/Vendor must execute and perform said Agreement. All bids must be firm for at least 120 days from the due date of the proposal. If, for by reasons of refusal by the vendor/contractor, a contract is not executed with the selected Bidder within 14 days after notice of recommendation for award, then the City may recommend the next lowest responsive and responsible Bidder for that zone
- 11) **NO RFP RESPONSE:** Bidders who receive this RFP but who do not submit a bid should return this RFP package stating "No Bid" and are encouraged to list the reason(s) for not responding. Failure to return this form may result in removal of the Bidder's name from all bidder lists.

- 12) FREEDOM OF INFORMATION ACT REQUIREMENTS: Proposals are subject to public disclosure after the deadline for submission in accordance with state law.
- 13) ARBITRATION: Contractor/Vendor agrees to submit to arbitration all claims, counterclaims, disputes and other matters in question arising out of or relating to this agreement or the breach thereof. The Contractor's agreement to arbitrate shall be specifically enforceable under the prevailing law of any court having jurisdiction to hear such matters. Contractor's obligation to submit to arbitration shall be subject to the following provisions:
 - (a) Notice of demand for arbitration must be submitted to the City in writing within a reasonable time after the claim, dispute or other matter in question has arisen. A reasonable time is hereby determined to be fourteen (14) days from the date the party demanding the arbitration knows or should have known the facts giving rise to his claim, dispute or question. In no event may the demand for arbitration be made after the time when institution of legal or equitable proceedings based on such claim dispute or other matters in question would be barred by the applicable statute of limitation.
 - (b) Within fourteen (14) days from the date demand for arbitration is received by the City, each party shall submit to the other the name of one person to serve as an arbitrator. The two arbitrators together shall then select a third person; the three together shall then serve as a panel in all proceedings. Any decision concurred by a majority of the three shall be a final binding decision.
 - (c) The final decision rendered by said arbitrators shall be binding and conclusive and shall be subject to specific enforcement by a court of competent jurisdiction.
 - (d) The costs of the arbitration shall be split and borne equally between the parties and such costs are not subject to shifting by the arbitrator.
- 14) **BID HOLD:** The City of Flint may hold proposals for a period of one hundred twenty (120) days from opening, for the purpose of reviewing the results and investigating the qualifications of bidders prior to making an award.
- 15) **NONCOMPLIANCE:** Failure to deliver in accordance with specifications will be cause for the City of Flint and they may cancel the contract or any part thereof and purchase on the open market, charging any additional cost to the Contractor/Vendor.
- 16) DISCLAIMER OF CONTRACTUAL RELATIONSHIP: Nothing contained in these documents shall create any contractual relationship between the City and any Subcontractor or Sub-subcontractor.
- 17) ERRORS AND OMISSIONS: Bidder is not permitted to take advantage of any obvious errors or omissions in specifications.
- 18) INTERPRETATION: In the event that any provision contained herein shall be determined by a court of competent jurisdiction or an appropriate administrative tribunal to be contrary to the provision of law or to be unenforceable for any reason, then, to the extent necessary and possible to render the remainder of this Agreement enforceable, such provision may be modified or severed by such court or administrative tribunal having jurisdiction over this Agreement and the interpretation thereof, or the parties hereto, so as to, as nearly as possible, carry out the intention of the parties hereto, considering the purpose of the entire Agreement in relation to such provision.
- 19) LAWS AND ORDINANCES: The bidder shall obey and abide by all of the laws, rules and regulations of the Federal Government, State of Michigan, Genesee County and the City of Flint, applicable to

- the performance of this agreement, including, but not limited to, labor laws, and laws regulating or applying to public improvement, local government, and its operational requirements.
- 20) **LOCAL PREFERENCE:** Vendors located within the corporate city limits of Flint, Michigan may be given a seven percent (7%) competitive price advantage. Additionally, if the lowest responsible vendor is not located within the limits of the City of Flint, but is located within the county of Genesee and vendor does not exceed the bid of the lowest non-local bidder by more than three and a half percent (3 ½ %), the County vendor may have a competitive advantage. City of Flint Business is defined as a sole proprietorship, partnership, limited partnership, limited liability company, or corporation whose primary place of business is located within the corporate limits of Flint, Michigan. Business must have made a personal property tax filing with a city or township treasurer within Genesee County within the last 12 months, or who has paid a real property tax assessment to a city or township treasurer within the City within the last 12 months.
- 21) MATERIAL WORKMANSHIP AND STANDARDS OF PERFORMANCE: The bidder agrees to exercise independent judgment and to complete performance under this Agreement in accordance with sound professional practices. In entering into this Agreement, the City is relying upon the professional reputation, experience, certification and ability of the bidder. The bidder agrees that all of the obligations required by him/her pursuant to this Agreement shall be performed by him/her or by others employed pursuant to this Agreement shall be performed by him/her and working under his direction and control. The continued effectiveness of this Agreement during its term or any renewal term shall be contingent, in part, upon the bidder maintaining his/her operating qualifications in accordance with the requirements of federal, state and local laws. All materials furnished must be new, of latest model and standard first grade quality or best workmanship and design, unless otherwise expressly specified. Bidder, if required, must furnish satisfactory evidence of quality materials; offers of experimental or unproven equipment may be disregarded.
- 22) MODIFICATIONS/CHANGES/PRICE VARIATIONS: Any modification to this agreement must be in writing and signed by the authorized employee, officer, board or council representative authorized to make such modifications pursuant to the State law and local ordinances. Commodities subject to market price variation shall be considered on all term agreements subject to a 30-day advance written notification from the vendor. Such notice must be substantiated by a written price change from the manufacturer and shall be required for both price increases and decreases.
- 23) NON-COLLUSION: The bidder acknowledges that by signing this document that he/she is duly authorized to make said offer on behalf of the company he/she represents and that said bid is genuine and not sham or collusive and not made in the interests or on behalf of any person not therein named, and that he/she and said bidder have not directly induced or solicited any other person(s) or corporation to refrain from responding to this solicitation and that he/she and said bidder have not in any manner sought by collusion to secure to himself/herself and said bidder any advantage over any other bidder.
- 24) NON-DISCRIMINATION: Pursuant to the requirements of 1976 P.A. 453 (Michigan Civil Rights Act) and 1976 PA. 220 (Michigan Handicapped Rights Act), the local unit and its' agent agree not to discriminate against any employee or applicant for employment with respect to hire, tenure, terms, conditions, or privileges of employment or a matter directly or indirectly related to employment because of race, color, religion, national origin, age, sex, height, weight, marital status or because of a handicap that is unrelated to the person's ability to perform the duties of nondiscrimination provision identical to this provision and binding upon any and all contractors and subcontractors. A breach of this covenant shall be regarded as a material breach of this contract.

- 25) **SUBCONTRACTING:** No subcontract work shall be started prior to the written approval of the subcontractor by the City. A list of possible subcontractors shall be submitted with the bid. The City reserves the right to accept or reject any subcontractor.
- 26) **WAIVER**: Failure of the City to insist upon strict compliance with any of the terms, covenants or conditions of this Agreement shall not be deemed a waiver of that term, covenant or condition or of any other term, covenant or condition. Any waiver or relinquishment of any right or power hereunder at any one or more times shall not be deemed a waiver or relinquishment of that right or power at any other time.
- 27) JURISDICTION OF OMBUDSMAN: Any person, business or other entity submitting a bid or bid in response to a request by the City consents to be subject to the jurisdiction of the Ombudsman of the City of Flint and to comply with the respective Charter provisions governing the Ombudsman's duties, jurisdiction and powers.
- 28) **PREVAILING WAGE:** The successful bidder providing any contractual labor services must comply with all state and federal requirements and pay wages and fringe benefits as governed under the Davis Bacon Act.
- 29) CITY INCOME TAX WITHHOLDING: Contractor and any subcontractor engaged in this contract shall withhold from each payment to his employees the City income tax on all of their compensation subject to tax, after giving effect to exemptions, as follows:
 - (a) Residents of the City:
 At a rate equal to 1 % of all compensation paid to the employee who is a resident of the City of Flint.
 - (b) Non-residents:
 At a rate equal to 1/2% of the compensation paid to the employee for work done or services performed in the City of Flint.

These taxes shall be held in trust and paid over to the City of Flint in accordance with City ordinances and State law. Any failure to do so shall constitute a substantial and material breach of this contract.

- 31) **CONTRACT/PROCUREMENT DOCUMENTS:** The invitation for bids, instructions to bidders, bid, affidavit, addenda (if any), statement of bidder's qualifications (when required), general conditions, special conditions, performance bond, labor and material payment bond, insurance certificates, (if required), technical specifications, and drawings, together with this agreement, form the contract, and they are as fully a part of the contract as if attached hereto or repeated herein.
- 32) **DISCLAIMER OF CONTRACTUAL RELATIONSHIP WITH SUBCONTRACTORS:** Nothing contained in the Contract Documents shall create any contractual relationship between the City and any Subcontractor or Sub-subcontractor.
- 33) **EFFECTIVE DATE:** Any agreement between the City and the contractor shall be effective upon the date that it is executed by all parties hereto.
- 34) FORCE MAJEURE: Neither party shall be responsible for damages or delays caused by Force Majeure or other events beyond the control of the other party and which could not reasonably have been anticipated or prevented. For purposes of this Agreement, Force Majeure includes, but is not limited to, adverse weather conditions, floods, epidemics, war, riot, strikes, lockouts, and other industrial disturbances; unknown site conditions, accidents, sabotage, fire, and acts of God. Should Force Majeure occur, the parties shall mutually agree on the terms and conditions upon which the services may continue.

- 35) **INDEMNIFICATION:** To the fullest extent permitted by law, Contractor agrees to defend, pay on behalf of, indemnify, and hold harmless the City of Flint, its elected and appointed officials, employees and volunteers and others working on behalf of the City of Flint, including the Project Manager, against any and all claims, demands, suits, or losses, including all costs connected therewith, and for any damages which may be asserted, claimed, or recovered against or from the City of Flint, its elected and appointed officials, employees, volunteers or others working on behalf of the City of Flint, by reason of personal injury, including bodily injury or death and/or property damage, including loss of use thereof, which may arise as a result of Contractor's acts, omissions, faults, and negligence or that of any of his/her employees, agents, and representatives in connection with the performance of this contract. Should the Contractor fail to indemnify the City in the above-mentioned circumstances, the City may exercise its option to deduct the cost that it incurs from the contract price forthwith.
- 36) **INDEPENDENT CONTRACTOR:** No provision of this contract shall be construed as creating an employer-employee relationship. It is hereby expressly understood and agreed that Contractor is an "independent contractor as that phrase has been defined and interpreted by the courts of the State of Michigan and, as such, Contractor is not entitled to any benefits not otherwise specified herein.
- 37) NO THIRD-PARTY BENEFICIARY: No contractor, subcontractor, mechanic, material man, laborer, vendor, or other person dealing with the principal Contractor shall be, nor shall any of them be deemed to be, third-party beneficiaries of this contract, but each such person shall be deemed to have agreed (a) that they shall look to the principal Contractor as their sole source of recovery if not paid, and (b) except as otherwise agreed to by the principal Contractor and any such person in writing, they may not enter any claim or bring any such action against the City under any circumstances. Except as provided by law, or as otherwise agreed to in writing between the City and such person, each such person shall be deemed to have waived in writing all rights to seek redress from the City under any circumstances whatsoever.
- 38) **NON-ASSIGNABILITY:** Contractor shall not assign or transfer any interest in this contract without the prior written consent of the City provided, however, that claims for money due or to become due to Contractor from the City under this contract may be assigned to a bank, trust company, or other financial institution without such approval. Notice of any such assignment or transfer shall be furnished promptly to the City.
- 39) NON-DISCLOSUREICONFIDENTIALITY: Contractor agrees that the documents identified herein as the contract documents are confidential information intended for the sole use of the City and that Contractor will not disclose any such information, or in any other way make such documents public, without the express written approval of the City or the order of the court of appropriate jurisdiction or as required by the laws of the State of Michigan.
- 40) RECORDS PROPERTY OF CITY: All documents, information, reports and the like prepared or generated by Contractor as a result of this contract shall become the sole property of the City of Flint.
- 41) SEVERABILITY: In the event that any provision contained herein shall be determined by a court or administrative tribunal to be contrary to a provision of state or federal law or to be unenforceable for any reason, then, to the extent necessary and possible to render the remainder of this Agreement enforceable, such provision may be modified or severed by such court or administrative tribunal so as to, as nearly as possible, carry out the intention of the parties hereto, considering the purpose of the entire Agreement in relation to such provision. The invalidation of one or more terms of this contract shall not affect the validity of the remaining terms.
- 42) **TERMINATION:** In the event of a failure by Contractor to perform any material provision of this Contract, the City or DEQ shall give written notice of such breach to the Contractor. The City may allow up to five (5) days (the "cure period") to correct such a breach. City may terminate this Contract after such cure period if Contractor has not adequately corrected such breach in accordance with this Contract and City so notifies Contractor in writing of such termination

action. At such time, City shall pay Contractor only all charges and fees for the services performed on or before such termination date. Thereafter, in the event such termination, City, as its sole and exclusive remedy may exercise its rights under Contractor's performance bond, and procure the services of another contractor to complete the work covered under this contract. If a cure period is allowed, it will not negate any liquidated damage charges resulting from the contractor failing to meet the completion date.

In the event of a failure by City to perform any material provision of this Contract, the Contractor shall give written notice of such breach to the City along with at least five (5) days (the "cure period") to correct such breach. Contractor may terminate this Contract after such cure period if City has not adequately corrected such breach in accordance with this Contract and Contractor so notifies City in writing of such termination action. At such time, City shall pay Contractor for all charges and fees for the services performed on or before such termination date. Thereafter, following any such termination and the final payment from the City to the Contractor, neither party shall have any further obligation under this Contract other than for claims for personal injuries or property damage as expressly provided in these terms and arising prior to such termination date.

In the event a Court of competent jurisdiction enters an order holding that this Contract is invalid, illegal, or unenforceable, then either party may terminate the Contract. At such time, City shall pay Contractor for all charges and fees for the services performed on or before such termination date. Thereafter, following any such termination and the final payment from the City to the Contractor, neither party shall have any further obligation under this Contract other than for claims for personal injuries or property damage as expressly provided in these terms and arising prior to such termination date.

- 43) **TIME PERFORMANCE:** Contractor's services shall commence after receipt of the notice to proceed and shall be carried out per the specifications of this document.
- 44) **EVALUATION OF BIDS:** In the City's evaluation of proposals, at minimum; firm's written proposal, the qualifications of the firm, the overall fee structure, feedback from references, and all requirements set forth in this document shall be considered as selection and award criteria unless otherwise as specified. The City reserves the right to enter into negotiations with the selected vendor for further clarification, even though these negotiations may result in minor changes to specifications and pricing.
- 45) **FURNISHING OF BONDS**: Contractor shall furnish to the City at his or her own cost, performance and payment bonds in the amount of the contract price insuring that it shall fulfill all of the provisions of the contract documents, shall satisfactorily complete the Work, and shall make prompt payment to all persons furnishing material or labor required in prosecution of the Work as required by law. Bonds must be issued by a surety company. Contractor's bonds shall be accompanied by powers of attorney authorizing execution of behalf of the surety and Contractor, and must be countersigned by a duly authorized Michigan agent of the surety. Selected Contractors will have the option of bonding the full amount of their award or a partial segment (zone) of their award. If Contractors elects to segment their bonding, Contractor must obtain approvals for the previous bonded work and initiate a new bond for the next segment (or zone). This process will be repeated until contract is complete. Refer to section entitled "Scope of Work" #4 for additional information. The performance and payment bond contract price shall be established as \$ [(¾" Partial Replacement Price Bid X 270) + (¾" Full Replacement Price Bid X 330)].
- 46) AMERICAN IRON AND STEEL (AIS) REQUIREMENTS: The Contractor acknowledges to and for the benefit of the city of Flint ("Purchaser") and the Michigan Department of Environmental Quality (the "State") that it understands the goods and services under this Agreement are being funded with monies made available by the State Revolving Fund and/or the Drinking Water Revolving Fund and such law contains provisions commonly known as "American Iron and Steel (AIS);" that requires all iron and steel products used in the project be produced in the United States ("AIS Requirements") including iron and steel provided by the Contractor pursuant to this Agreement. The Contractor

hereby represents and warrants to and for the benefit of the Purchaser and the State that (a) the Contractor has reviewed and understands the AIS Requirements, (b) all iron and steel used in the project will be and/or have been produced in the United States in a manner that complies with the AIS Requirements, unless a waiver of the requirements is approved or the State made the determination in writing that the AIS Requirements do not apply to the project, and (c) the Contractor will provide any further verified information, certification or assurance of compliance with this paragraph, or information necessary to support a waiver of the AIS requirements, as may be requested by the Purchaser. Notwithstanding any other provision of this Agreement, any failure to comply with this paragraph by the Contractor shall permit the Purchaser or State to recover as damages against the Contractor any loss, expense or cost (including without limitation attorney's fees) incurred by the Purchaser or State resulting from any such failure (including without limitation any impairment or loss of funding, whether in whole or in part, from the State or any damages owed to the State by the Purchaser). While the Contractor has no direct contractual privity with the State, as a lender to the Purchaser for the funding of its project, the Purchaser and the Contractor agree that the State is a third-party beneficiary and neither this paragraph (nor any other provision of this Agreement necessary to give this paragraph force or effect) shall be amended or waived without the prior written consent of the State.

47) **INSURANCE REQUIREMENTS:** The Contractor shall notify all insurance agents and companies retained by the Contractor that these insurance requirements shall be included in any Agreement between the Contractor and the City of Flint. The Contractor shall purchase and maintain, at its sole expense and as long as it is providing services to the City, the following insurance coverage:

Commercial General Liability – Occurrence form, including coverage for bodily injury, personal injury, property damage (broad form), premises/operations, blanket contractual, and products/completed operations. Coverage shall be endorsed to include the City as an additional insured for work performed by the Contractor in accordance with the Agreement.

Minimum Limits:

- \$1,000,000 per occurrence/\$2,000,000 general aggregate
- \$2,000,000 aggregate for products and completed operations
- \$1,000,000 personal and advertising injury

Automobile – Michigan "no-fault" coverage, and residual automobile liability, comprehensive form, covering owned, hired, and non-owned automobiles. Coverage shall be endorsed to include the City as an additional insured for work performed by the Contractor in accordance with the Agreement.

Minimum Limits:

- No-fault coverages statutory
- \$500,000 per person/\$1,000,000 per accident bodily injury
- \$500,000 per occurrence property damage
- A combined single limit of \$1,000,000 per occurrence

Workers' Compensation and Employer's Liability-Statutory coverage or proof acceptable to the City of approval as a self-insurer by the State of Michigan.

Minimum Limits:

- Workers' Compensation statutory
- Employer's Liability \$100,000 each accident/\$100,000 disease each employee

\$500,000 disease – policy limit

Professional Liability – Covering acts, errors or omissions of a professional nature committed or alleged to have been committed by the Contractor or any of its subcontractors. Coverage shall be effective upon the date of the Agreement and shall remain effective for a period of three (3) years after the date of final payment thereunder. Such coverage shall be endorsed to include any subcontractors hired by the Contractor.

Minimum Limits:

• \$1,000,000 per occurrence, \$1,000,000 annual aggregate

Insurance coverage shall cover all claims against the City of Flint, its officials and employees, arising out of the work performed by the Contractor or any subcontractors under the Agreement. Should any work be subcontracted, it shall be the responsibility of the Contractor to maintain Independent Contractor's Protective Liability Insurance with limits equal to those specified above for Commercial General Liability Insurance. In addition, the Contractor shall provide proof of Workers' Compensation Insurance for all subcontractors in compliance with the required statutory limits of the State of Michigan.

Said policies of insurance shall be with companies licensed to do business in the State of Michigan and in a form satisfactory to the City. All insurance companies must maintain a rating of B+, VIII or better from A.M. Best Company. Certificates of insurance with a thirty-(30) day cancellation clause shall be filed with and approved by the City at least five (5) days in advance of commencing work under the Agreement. Cancellation, material restriction, non-renewal or lapse of any of the required policies shall be grounds for immediate termination of the Agreement by the City.

The City reserves the right to request a complete certified copy of the policies for the above coverage's.

Any reduction or exhaustion in the limits of required insurance coverage shall not be deemed to limit the indemnification afforded in accordance with the Agreement or any amendments thereto.

Depending on the subject matter of the transaction, the City may require other insurance coverage in addition to the coverage's contained herein.

Proposal Submission

Release date: Thursday, February 16, 2017 by 5:00 PM (EST)

Proposal Due Date: Friday, March 3, 2017 by 10:A0 PM (EST)

Submit to City: 1 printed, signed, original proposal and signed addenda,

1 copy of all submitted documents

1 unbound copy of proposal.

Send to: City of Flint Department of Purchases & Supplies 1101 S. Saginaw St., Rm. 203

Flint, Michigan 48502

Important Notice:

Effective immediately upon release of this request for proposal (RFP), and until notice of contract award, all official communications from proposers regarding the requirements of this RFP shall be directed to:

Derrick F. Jones 810 766-7340 djones@cityofflint.com

The City, or designee, shall distribute all official changes, modifications, responses to questions or notices relating to the requirements of this RFP. An addenda to this RFP may be developed and shared with all Vendors. Any other information of any kind from any other source shall not be considered official, and proposers relying on other information do so at their own risk.

Anticipated Timeline Overview

Listed below are specific and estimated dates and times of actions related to this request for proposal (RFP). The actions with specific dates must be completed as indicated unless otherwise changed. In the event that it is necessary to change any of the specific dates and times in the calendar of events listed below, an addendum to this RFP will be issued.

Milestone	Timeframe
RFP issuance and release	Thursday, February 16, 2017 after 3:00 PM
RFP posted to City's website	Thursday, February 16, 2017 after 5:00 PM
Place Ad in Newspaper, periodicals	Ad will run on Sunday, February 19, 2017
Final Deadline to submit questions concerning proposal or information discussed during the pre-bid meeting.	Thursday, February 23, 2017 by 5:00 PM
City to issue an addendum to respond to any questions received and any outstanding issues.	No later than Monday, February 27, 2017
Proposal Due Date	Friday, March 3, 2017 before 10:00 AM (EST)
Review of proposals	March 6-10, 2017
Submit selected vendor(s) to City Council for	Monday, March 13, 2017 (Committee Meeting),
review	Monday, March 13, 2017 (Council Meeting)
If approved by City Council, selected vendors will be presented to RTAB for review	TBD

Any written questions regarding this project shall be directed to Derrick Jones @ djones@cityofflint.com using the subject title of "RFP 17-564 - Question." Questions may be submitted before Thursday, February 23, 2017 before 5:00 PM (EST), and responses will be addressed in the addendum that will be issued no later than Monday, February 27, 2017.

Derrick F. Jones, Purchasing Manager

Sincerely

Department of Purchases & Supplies

INTRODUCTION

Information about the City of Flint

The City of Flint (the City, or COF), incorporated in 1855, is located in the eastern part of the State of Michigan. The City currently occupies a land area of 32.8 square miles and serves a population of 111,475 (2010 Census Estimate). The City is empowered to levy a property tax on both real and personal properties located within its boundaries, as well as a 1% income tax for those who live within the City limits, or .5% for those who only work within the City limits. The City does not collect a fee from its residents; however, a three percent (3%) millage is assessed on properties within the City's boundaries.

The City has operated under the strong mayor- Council form of government since November 4, 1975, when the present charter was adopted. Legislative authority is vested in a City Council consisting of nine members elected for a four-year term (no term limits), from each of the nine wards in the City. The City Council is responsible for passing ordinances, adopting the annual budget, approving resolutions, appointing committees, and other responsibilities as outlined in the City's Code of Ordinances. The Mayor is an elected official who serves as the chief executive officer of the City for a four-year term, in which he/she may be re-elected for additional terms. The Mayor may appoint a City Administrator to handle the day-to-day-operations for the municipality. On November 29, 2011, the governor of Michigan appointed an emergency manager, pursuant to Public Act 4 of 2011, to handle all of the day-to-day operations for the City. Considerable progress was made in reducing the deficit, whereas by June 30, 2015 a positive fund balance was realized. As a result of many financial achievements of the City, Governor Snyder has declared that the City's financial emergency has been resolved. With oversight from a receivership transition advisory board (RTAB), City operations have returned have been partially returned to the Mayor and Charter-designated leaders.

Water Line Replacement Project

An analysis of service lines has been performed for the City and it has been determined that there is a need to replace said service lines in different areas of the City. The focus of the replacement will be in neighborhoods with the greatest density of lead and galvanized service lines. Replacement of these service lines has been determined to be the best remedy in restoring the integrity of the drinking water system.

It is most recently estimated that there could be as many as 29,100 non-copper (partial or full) water service lines in the City of Flint. Approximately 22,500 of these could be to occupied parcels. This data will be continuously updated for later phases of service line replacement.

The City has received funding from the State and Federal Government for this project. Please note that contractors will have to comply with state and federal terms and conditions that are included in this proposal as articulated in Exhibit E. Contractors must review, comply, complete, and submit the appropriate documents that are included in this exhibit.

This RFP is for the fourth phase of service line removal which will include the removal and replacement of lead and galvanized service lines to as many homes as possible, with the goal to replace as many lead and galvanized lines as possible prior to the end of 2017. The City has designated the areas for service line replacement based upon a combination of the criteria discussed above — as well as census data and water sample results.

The City will continue to validate the accuracy of the City Water Department records on the composition of the residential service lines as well as gain further needed knowledge on the depth of the lines, soil composition, age of homes most likely to have a lead service line, the methods used for original line installation, the effects of the corrosivity on service lines, and to better assess the method and costs of service line replacement. Thus, successful bidders will be required to cooperate in data collection on all replacement locations.

Scope of Work

Requested Services

The City is seeking a General Contractor, or the like, that has at least five (5) years' worth of experience in replacing service lines in order to perform the replacement of service lines to various residential homes/buildings located within the City of Flint. The selected vendor will have a designated individual who will perform as a "project manager," or like, in which the City will provide direction and receive timely updates as to vendor's progress on this project. This project work shall consist of replacing service lines by excavating streets and/or yard areas, removing existing lines, installing copper water service lines, extending service lines into the interior of houses, patching pipe penetration, and temporary restoration. Vendors should be capable of installing water service lines using trenchless technology and equipment. Vendors may submit proposals that utilizes a different methodology as described in this RFP, however, said methodology will have to be approved by the City and the vendor will have to articulate the full process in which they will install service lines within their proposal. If vendors are awarded a contract and are seeking to expand their workforce to accommodate the contract, the City encourages hiring and training (i.e. an apprentice program) residents that reside within the City's corporate limits in order to fulfill the vendor's requirements.

- Requirement All project installation work shall be completed in conformance with the general conditions and construction specifications established by the City of Flint, Michigan Department of Transportation (MDOT) and any other provisions established herein.
- 2. **Utilities** The selected Contractor shall be responsible for obtaining utility locations from the MISS DIG System. Contractor shall be responsible for conducting an evaluation to assess the nature, depth and location of all sewer mains and laterals. If the contractor uses an installation method that requires the exposing of utilities, the contractor shall solely be responsible for the cost of the excavation, hand digging, and backfilling regardless of the location of the utility. If the utility is located in a paved area, the contractor shall backfill to grade according to City of Flint standards (included). The City, or a designated contractor, will complete the paving work.
- 3. Subcontractors The Contractor shall submit a list of all subcontractors that may be used on the project to assist with project work. The City will certify that they have checked SAM.gov to ensure no contractors are on the federal debarment/suspension list. All subcontractors must be approved by the City, and the City reserves the right to accept or reject any subcontractor.
- 4. Contract Time The Contractor shall begin work immediately after receiving the notice to proceed from the City. Along with the notice to proceed, the City will provide a list of approximately half of the zone's total locations. The contractor shall complete all line replacements of said locations at an average pace of 4.5 locations per work day. If a contractor is awarded multiple zones, a timeline shall be maintained separately for each zone, beginning with the notice to proceed for that zone, and a pace of 4.5 locations per work day shall be performed for each zone. Work day shall be considered Monday-Friday excluding all City of Flint holidays.

Construction work will not be allowed on Saturday or Sunday without approval from the COF Water Services Dept, Streets Dept, and BSI Department (if a plumbing permit was necessary). Any cost incurred for overtime utilized to stay on schedule will be at the contractor's expense.

Locations may be removed by the City of Flint if new information deems replacement at those addresses impossible or unnecessary. The contractor will be notified by the City as soon as that information is available. The City may offer replacement addresses in the same vicinity.

The City may also add locations if new information deems a replacement is necessary. Once the first half of a zone has been completed, the contractor may continue with the second half if a full performance bond has been posted (See "Instructions to Vendors – Item #45). If the contractor has only posted a performance bond for half of the zone work, the contractor must obtain all required approvals for the completed work, and initiate a new bond for the second half prior to commencing work on the next half. A second notice to proceed will be issued, after receipt of the new bond, for the second half of the zone.

- 5. Liquidated Damages Liquidated damages will be assessed for failure to meet the above schedule. Liquidated damages of \$1,550 will be assessed per work day (Monday-Friday) after the contract completion work days (as calculated by the number of locations divided by 4.5) has expired. Liquidated damages will be assessed upon completion of the total zone addresses. Each half zone will be considered separately. Time extensions will only be granted for delays not caused by the Contractor or the Contractor's methods. Time extensions shall also not include standard construction delays such as utility issues, problems locating facilities, lack of coordination with residents due to the contractor, or a delay of up to an hour for City Inspection. The contractor shall maintain a log of all other delays and shall submit the list by email no later than 72 hours after the end of each work week. Upon verification and approval by the City, the time will be added as a work day extension in increments of 1/8 day. Delay shall also be divided by the total number of crews working in each zone.
- 6. Resident Communication/Permission The City will provide a general communication piece for the residents as it relates to what the project entails, along with a copy of a consent agreement that will be executed by the home owner. Vendor will have to communicate with awarded neighborhoods and residents to provide this information and to obtain the required signatures. Vendor is to inform residents of the work that will be performed along with a time frame in which a resident's home will undergo construction. The vendor will allow adequate time to provide the property owner and/or resident five (5) calendar days advance notice of the day work is to occur on their property. Notification of water shutoff shall also be provided to the resident on the morning of the day work is to be performed. Information disseminated to residents must reflect any instructions that will have to be performed by the homeowner (resident) during and after the construction.
- 7. Coordination of Work with City Representatives Contractor will be responsible for notifying designated individuals at the City of Flint Streets, Water Services and BSI departments, as well as the designated City project manager. The Water Services Dept intends on installing new water meters at the time of replacement. This labor will be performed by City crews.
- 8. Suspension of Operations The City or DEQ can suspend operation of work without cost to the City/DEQ if the Contractor has failed to correct unsafe conditions, failed to carry out provisions of the contract, conditions deemed to be in the public interest, when City has determined that additional excavations in needed prior to installation of service

- lines, and when quality or quantity of work being performed is not in adherence to the project specifications or schedule.
- 9. Permits Vendor will be responsible to obtain any required permits prior to commencing work including the excavation permit, street cut permit, water services permit and the plumbing permit (if needed any movement of the meter or an alteration/extension beyond the meter will require a plumbing permit). NO PERMIT FEES WILL BE CHARGED TO THE CONTRACTOR for required work on this contract. A certificate of approval from the Water Services Dept will be required prior to payment for any location. Approvals from the Streets Dept and any Plumbing Permits will be required prior to retainer release.
- 10. Contract Work Schedule and Project Coordination Vendor shall be responsible for coordinating and scheduling all project work to avoid conflicts with other construction activities occurring in and near project areas. The contractor will also be required to coordinate with government or university representatives taking water and/or pipe samples, and COF Water Services who will install new meters.
- 11. Traffic Control Contractor shall be responsible for the placement, maintenance, and removal of all traffic control signs, barricades and fencing necessary to protect the public and residents from injury. No work shall be allowed after sunset without proper lighting and clothing per the current MMUTCD and MDOT Specifications for Construction. Work after sunset is at the contractor's expense and shall be completed by 8pm. Any work on major streets will require a work zone traffic control set-up, and must be coordinated with City representative Rod McGaha. You may contact Mr. McGaha @ 810-766-7135 then press 8.
 - Whenever small openings such as "window cuts" are made in a road pavement that must remain open to traffic during the time there is no work activity, they shall be covered with steel plates. The steel plates shall be of adequate size and thickness (minimum ¾") to support all legal axle loads and shall overlap existing pavement by at least two feet on all sides of the hole.
- 12. Service Line Installation Procedures Non-standard (lead and galvanized iron pipe) water service lines may exist between the watermain and curb box; or between the curb box and water meter located inside the house (or in a meter pit outside of the house/building). In other instances, the entire water service line from water main to meter may consist of non-standard materials. Contractors will perform the work as follows:

Pre-construction Procedures

- a) _____Contact Property Owners and Residents as stated above. Obtain Private Property Consent for access. Prior to conducting any construction work, the contractor is to document asking the homeowner what appliances and fixtures have water connections and explain that those items need to be properly flushed out with any sediment catching devices removed (filters, aerators, etc.). The flushing is to be performed by the contractor, and the contractor shall document that the flushing was performed properly and filters, aerators, etc. were replaced after completion. For partial replacements where homeowner permission was not granted, the contractor is to leave instructions stating the above information for the property owner and document when and where the information was delivered. All documentation shall be submitted to the City on a regular basis.
- b) ____Obtain Water Service Replacement Permits (No Charge)
- c) ____Submit Indemnification Insurance Certificates to the City of Flint Finance Department

Notify City of Flint – Department of Transportation – Traffic Engineering, a minimum of 3 working days of Temporary Maintaining of Traffic Plans for streets affected by water service replacements. Also notify Department of Water Services, and Department of Building Safety and Inspection. Notify Miss Dig 72 hours prior to construction.
Provide video of outside property and house interior (vicinity of meter) prior to start of construction.
Provide video of the sewer lateral from main to building prior to start of construction.
Provide a communication plan for all awarded areas. Contact the DEQ or the water sampling agency at least five days prior to replacement, so water sampling can be done.
A procedure for watermain emergency work will be provided to the contractor. All ve turning and watermain work shall be completed by the COF Water Services pt.
nstruction Procedure
pical Site (residential home on residential street) Procedure/Specification:
The contractor shall be responsible to assure all valves serving the house/building a turned off to prevent particles from entering the water system. No segment of water service line shall be used for water service until all non-standard segments a replaced.
Locate starting excavation area per location (Watermain or Curb Stop) Water Services will mark the water infrastructure to the best of their ability. It is the contractor's responsibility to trace and locate the curb stop/box and watermain connection. In most cases, these connection locations may not be clearly apparent without investigation. No additional payment will be made for locating work.
Excavate to identify water service material If lead or galvanized material is identified, replace the service line segment, curb stop with box, and connections. If a ¾" or 1" corporation is in good, working order – the contractor is to use the same corporation. On larger lines, the corporation is to be re-tapped and the Contractor shall seek guidance from the COF Water Service Center. All connections shall be per the Plumbing Code. See Appendix #3 for a list of Specified materials and Approved Parts. Replacement lines shall be ¾" Type K Copper. If a service larger than 1" is found, notify the Water Services Dept. for a replacement size decision. Water services are to be installed a minimum 48" below the surface and shall be 60"

joints or connections between the watermain and curb stop, or curb stop and meter. If work is required on water main, it shall be completed by City of Flint

Water Service Center personnel only.

d) _____If lead or galvanized material is identified in a segment not intended to be replaced, notify the City immediately. Water service lines shall be perpendicular to buildings and main having no curves between building and main (preferred, if possible). Trenchless installation of water services using push bores, directional drilled, cable method and other approve methods shall use standard, approved construction methods. The contractor shall submit a boring plan detailing equipment, materials and procedure to be used prior to beginning work. Contractor will be responsible for approved repair to any damaged utility facilities at no additional cost to the contract. _All excavations necessary to complete the water service replacement (under roadways, curbs, driveways, approaches, and sidewalks must follow the attached utility trench details to at least 95% of the materials maximum density. All such excavations shall be capped off with a minimum of 8" of 23A limestone aggregate in the thickness under sidewalks, driveways, and approaches. A minimum of 12" of 23A limestone is required under all roadways and curb lines. These temporary restorations will be maintained by the vendor until the City has performed the final restoration. The vendor will be responsible for maintaining these areas for a maximum of 30 calendar days. All excavations with the lawn/green belt areas are to be backfilled with the excavated material, well graded and free of any debris. These excavations will be filled to the level of the adjacent ground and left smooth. Final restoration will be performed by the City or a designated contractor. **Post-Construction Items** a) All joints, fittings and valve connections shall be exposed during a test period. The vendor will contact the City (the Water Service Center) in order for an inspection to be performed to ensure that work has been done correctly and to properly record the work for the City's annals. All newly installed service lines shall be flushed for at least two (2) minutes and pressure tested in accordance with the City of Flint specifications. Testing shall consist of installing a pressure gauge on the water service line to normal water main pressure. The test is run for five (5) minutes, and if there is no loss in pressure during the period, the service line will be considered as having passed the pressure test. The contractor shall locate and repair service lines which do not pass the pressure test. _After reconnection of the service line, flushing protocol will commence by b) running an outside faucet for a period of at least fifteen minutes to further flush any foreign material from the service line, and then flushing of all taps for at least fifteen minutes. Vendor will advise resident to continue to use filter for a period of

All work on replacing water service is completed, including "temporary"

restorations in paved areas and permanent restoration in green areas.

until further notice.

- d) _____All documents related to replacing the water service line have been completed. A website link will be provided to the Contractor which will bring up a form to be completed. Minor additional documentation may be required for invoicing.
 e) _____All documents provided to all necessary agencies including the City of Flint Water Service Center.
 f) _____Provide video of the sewer lateral from main to building to ensure the sewer line was not damaged.
 g) The contractor shall conduct an inspection of the internal plumbing to determine potential impacts on fixtures due to the replacement work. This inspection will be documented.
 h) _____ Proper inspections must be performed by City Departments (BSI, Street Maintenance, and Water Service Center)
- 13. **Meetings and Documentation** –Vendor will be required to submit daily reports documenting their work at each location. Vendor will also be required to participate in pre-construction meetings as needed to ensure all parties are in agreement.
- 14. Standard Replacement Specifications Except for excavations necessary to expose the water main and curb box, service lines shall be installed by use of trenchless technology methods unless otherwise approve by the City of Flint. The preferred method for replacing lead services is the cable method, which involves the use of a cable placed inside the existing lead service line with the new replacement copper line attached on the other side. The cable is then pulled using a winch or backhoe bucket to remove the old service line while pulling in the new copper line. This process is used separately for the service line between the main and curb box and between the curb box and house. If the old service line cannot be removed by the cable method, the new service line would need to be installed by use of boring equipment.
 - A. From Water Main to Curb Box (Public Partial)

For non-standard service lines located between the water main and curb box, the vendor shall excavate the service line at two locations; at the water main, which is typically located beneath the street pavement, and at the curb box, typically located near the sidewalk. The old service line will then be disconnected at the water main and curb stop and a new copper service line is then installed. The new copper service line will then be connected to the old corporation valve on the existing water main using appropriate adaptors and fittings. Existing corporations are typically ¾" in diameter and transition fittings may be required for connection to the new service lines. If a standard service line (copper) exists between the curb box and house/building, the vendor will connect the new service line to the existing curb box after first flushing the new service line from main to curb box. The City is requiring that vendor replace the curb stop at these locations.

B. From Curb Box to House (Private Partial)

For non-standard lines located between the existing curb box and house, the vendor shall excavate and replace the curb stop/box, which is typically located near the sidewalk or property line. The water service line inside the house/building on the inlet side of the water meter shall also be disconnected by the vendor. The opening in the wall at the location where the service line extends through the foundation of the house/building shall then be enlarged by the contractor if necessary. The new copper service line will then be installed between the house and curb box. The vendor shall extend the new service line into the home/building and connect the line

to the water meter. If it is necessary to use boring equipment to install the service line, the boring equipment shall bore through the foundation/basement wall of structure and the old service line shall be abandoned on the inside of the basement wall by removing at least two (2) inches of the lead service lines from within the basement wall, filling the interior of the remaining pipe with mortar. If it becomes necessary for the vendor to excavate on the outside of the building foundation to facilitate installation of the water service line, such work shall be completed in a manner that causes the least amount of disruption to yard areas and other locations near the home/building. The vendor will contact the City (the Water Service Center) in order for an inspection to be performed to ensure that work has been done correctly and to properly record the work for the City's annals.

C. From Water Main to House (Full)

Where the entire water service line (water main to building) consist of non-standard materials, the vendor shall follow the installation procedures described above and also install a new curb stop valve and curb box near the sidewalk at a location approved by the City. The vendor will contact the City (the Water Service Center) in order for an inspection to be performed to ensure that work has been done correctly and to properly record the work for the City's annals.

D. Copper Service Line Found from Water Main to House

Where the entire water service line consists of standard materials (copper) from the main to the house, the vendor shall place a new curb box and restore the site to original conditions. The vendor will contact the City (the Water Service Center) in order for an inspection to be performed to ensure that work has been done correctly and to properly record the work for the City's annals.

In all cases, prior to reconnecting the water meter, the new service line shall be thoroughly flushed with sufficient water volume and velocity to remove all foreign material from within the pipe. If material within the pipe damages or plugs a customer's meter or service piping, the vendor shall be responsible for the cost of all repairs to the service line and related plumbing.

After reconnection of the service line, flushing protocol will commence by running an outside faucet for a period of at least fifteen minutes to further flush any foreign material from the service line, and then flushing of all taps for at least fifteen minutes. Vendor will advise resident to continue to use filters until further notice.

15. Unusual Replacement Situations -

- A. In the event that a shared service line is discovered, the Contractor shall place separate service lines to each home and shall be paid separately for each service line.
- B. In the event that an abandoned house lead is encountered, the Contractor shall cut and cap the service line to the abandoned house at the main. The Contractor shall note the abandoned home and the disposition in weekly reports.
- C. In the event that tree or tree roots prevent installation, a bid item for tree removal is included in this document. The bid item shall include all work necessary to eliminate the tree and roots from interfering with the installation, as well as the stump grinding or restoration necessary to bring the yard to a uniform grade. If a tree is an issue, notify the Water Services Department for a decision on whether the tree should be removed or a relocated line shall be used prior to taking action.
- D. In the event that a partial service line is expected, but it is found that a full replacement is needed, the Contractor shall perform a full replacement at the proper bid item price.

- E. In the event that a line is excavated and found to be copper, the Contractor shall place a new curb box, backfill and restore the excavated area. A bid item is established to pay for this situation.
- 16. Excavation Vendor shall furnish all labor, equipment and materials necessary to expose all necessary appurtenances to replace the existing water service line as directed. Except where otherwise approved by the City, vendor will saw cut pavement/curb/sidewalk to an appropriate dimension to carry out the appropriate repair. and the excavation and installation process shall be performed in a manner to allow placement of the new service line at a final cover depth of (five) 5 to (six) 6 feet below finished grade regardless of the depth of the existing water service or water main. Pavement cuts are expected to be no larger than 10'x10', curb removals no more than 10' and sidewalk removals of no more than 2 flags. Excessive damage will not be tolerated and will be charged against the retainer. Larger removals necessary for safety shall be reviewed with City staff. The pavement sawcut shall be clean and square. If the sawcut edge is damaged during construction, it shall be re-sawcut upon construction completion. If excavated roads contain pavement bricks, the bricks shall be excavated in a manner that minimizes damage to the bricks. The bricks shall then be set in a safe location for City personnel to retrieve, and the Streets Department notified. No additional compensation will be granted for the salvaging of the bricks. Except where otherwise approved by the City, all excavations necessary to complete the water service replacement (under roadways, curbs, driveways, approaches, and sidewalks) must follow the utility trench details (see Appendix 1) to at least 95% of the materials maximum density. Compaction within the influence of water, sewer or storm lines shall be completed with a plate compactor. All such excavation shall be capped off to final grade with a minimum of 8" of 23A limestone aggregate in the thickness under sidewalks, driveways, and approaches. A minimum of 12" of 23A limestone is required under all roadways and curb lines. These temporary restorations will be maintained at the contractor's expense until the City has performed final restoration (up to 30 days). All excavations within the lawn/green belt areas are to be backfilled with the excavated material, well graded and free of any debris. These excavations will be filled to the level of the adjacent ground and left smooth. The City or a designated contractor will perform final restoration of lawn and green belt areas.
- 17. Resident Courtesy The contractor, subcontractors, and all members of the construction crew shall continuously use all courtesies when working with the residents and their property. Such practices include, but are not limited to, using foot covers when inside the home, using electric saws, and performing dust control to minimize any air contamination. Contractors shall minimize property disturbance to the minimum necessary disturbance in order to complete the replacement work.
- 18. **Service Line Material** Any service line material removed from the ground is City property and shall be given to Water Service personnel or delivered to a location specified by the Water Services Dept.
- 19. Contaminated Soil If unknown areas of contaminated soils are encountered, the Contractor shall notify the DEQ and City. The Contractor shall share the plan of action for the contaminated soil area with the DEQ and City prior to implementation. Storage and disposal of contaminated soil shall be in accordance with all local, State and Federal solid and hazardous waste laws and regulations.
- 20. Spills Contractors shall clean up all leaks and spills from containers and other items on or off site. Immediate containment shall be taken as necessary to minimize the effect of any spill or leak. The City shall notify the DEQ and City of the incident. Cleanup shall be in accordance with applicable Federal, State, and Local laws and regulations at no additional cost to the DEQ or City.

- 21. Storage of Materials and Equipment Contractors shall make all arrangements and provisions necessary for the storage of materials and equipment. Materials and equipment shall be kept neatly and compactly stored in locations that will cause a minimum of inconveniences to other contractors, public travel, residents, tenants, occupants, and businesses. Replacement material shall be stored in a secured location. Selected Contractors will have to obtain permission from property owners in order to store materials and equipment.
- 22. Cleanup of Soils, Waste, Rubbish, Debris, and Litter Contractor shall remove and dispose of any soils, waste, rubbish, debris, and litter in accordance with federal and state law and local ordinance.
- 23. Safety Vendor(s) will furnish the City written detailed safety procedures that will be instituted to maintain selected vendor(s) and their subcontractor employee's safety on awarded job sites. The procedures should address the manner in which vendor will meet the following requirements:
 - A. Vendor will adhere to all safety procedures (or processes) that have been mandated by all applicable federal and state safety regulations, safe practice, using materials, tools and rigging of a safe character. Vendor shall strictly comply with these laws, rules, and regulations including, but not limited to, OSHA and MIOSHA requirements, including without limitation MIOSHA "Right to Know" obligations, Michigan Occupational Safety and Health Act of 1974, and shall provide documented evidence of compliance upon request.
 - B. Vendor shall provide and use all necessary guards, railings, barricades and other protective devices to permit a safe working environment for vendor's employees, other contractors in the area of work site, City employees, and the public.
 - C. The employees of the vendor shall wear the appropriate safety protective gear such as safety glasses, side shields, hearing protection, and any other gear deemed required to wear within construction site.
 - .D. Vendor shall comply with OSHA and MIOSHA confined space requirements and procedures.
 - E. Vendor must make the City aware of safety violations or any injuries that have occurred on job sites.
 - F. Vendors shall wear an identifiable badge at all times. Entry into houses will be limited to authorized workers whose duties are to complete inside work.
- 24. **Warrant** Vendor(s) warrants the Project will be habitable and constructed in a good and workmanlike manner and free from defects in material and workmanship for a period of one year following the date of completion
- 25. Results to date The following information is for informational purposes only. The City of Flint makes no claims that this information will be applicable to the zones of construction in this RFP. Bidders are expected to make their own determination of approximate line lengths and replacement locations for bidding purposes through field review and/or other sources:

Results from the first over 700 replacements:

Average Length of Public Side Partial Replacement Only: 25 Ft (50% of Total)

Average Length of Private Side Partial Replacement Only: 30 Ft (3% of Total)

Average Length of Full Replacement: 67.5 Ft (47% of Total)

Average Length of all Replacements: 45 Ft

Average Occurrence of a Full Copper Line at a Location: 1 in 6.8

APPENDIX

Appendix 1 – City of Flint Backfill Requirements

Appendix 2 - A plan view sketch of service line replacement

Appendix 3 – Approved Parts List

APPENDIX 1

CITY OF FLINT BACKFILL REQUIREMENTS


Appendix 1 – City of Flint Backfill Requirements

UTILITY TRENCH EXCAVATION (for repair/replacement of public or private utility)

- Provide a safe working excavation by providing bracing (trench box, sheeting, etc.). If needed, cut back slopes to stable conditions.
- Clear excavation around utility to be repaired/replaced. Provide excavation to "good" piece of utility plus two (2) feet. Excavate to a minimum of twelve (12) inches below utility or sound material (judgment call in the field).
- If excavation is wet, attempt to pump it "dry" and stable. If it can't be pumped "dry" place small stone (pea stone) in bottom of excavation up to bottom of utility.
- Complete utility repair/replacement.
- Place Class II sand backfill up both sides of utility. This shall be compacted in no more than twelve (12) inch lifts. If diameter of utility is less than twelve (12) inches, compact once backfill is at top of utility. Continue with class II material until twelve (12) inches above utility.
- Place crushed 23A limestone to within approximately nine (9) inches (winter construction) or three (3) inches (summer construction) of finish grade.


UTILITY TRENCH DETAIL

UNDER ROADWAY




UTILITY TRENCH DETAIL

UNDER SIDEWALK



APPENDIX 2

A PLAN VIEW SKETCH OF SERVICE LINE REPLACEMENT



CITY OF FLINT WATER SERVICE REPLACEMENT PLAN VIEW SKETCH

APPENDIX 3

APPROVED PARTS LIST

:

Appendix #3 - Approved Parts List

	ildix #3 - Apploved Pall	.o Lioi
ITEM ID	DESCRIPTION	YOM
6700002000	A.M.S. w/handles 3/4"	EA
	Ford #KV23-332, HT-3	
6700146000	Corporation Sto0p, Cop 3/4"	EA
	Ford #F-600-3	
6700116000	Coupling, cop-cop 3/4"	EA
	Ford #C22-33	
6700125000	Coupling, cop-iron 3/4"	EA
	Ford #C28-33	
6700175000	Coupling, cop-cop 3/4"	EA
	Ford #C44-33	
6700160000	Curb stop, cop 3/4"	EA
	Ford #Z22-333	
6700246000	Curb stop, iron 3/4"	EA
	Ford #Z11-333	
6700178000	Coupling, iron 3/4"	EA
	Ford #Q28-33	
6700439000	Valve, cop 3/4"	EA
	Ford #B21-233D-HB-2	
6700439020	Valve iron, 3/4" (iron C&W)	EA
070000000	Ford #B11-233D-HB-2	
6700002040	Coupling, Meter 3/4" x 2."	EA
070040000	Ford #C38-23-2.5	
6700133000	Coupling, Compression 3/4"	EA
070007050	Ford #C84-33	
6700237050	Coupling, angle meter 3/4"	EA
6700147000	Ford #L38-23	
6700147000	Corporation stop 1"	EA
6700118000	Ford #F-600-4	
6700118000	Coupling, cop-cop 1" .	EA
6700114000	Ford #C22-44	
0700114000	Coupling, cop-iron 1" Ford #C28-44	EA
6700176000	Coupling cop-cop 1"	
0700170000	Ford #C44-44	EA
6700157000	Curb stop, cop 1"	Ε.Δ
0100101000	Ford #Z22-444	EA
6700246020	Curb stop, iron 1"	EA
01 002 10020	Ford #Z11-444	EA
6700171000	Coupling, iron 1"	EA
-, -, -, -, -, -, -, -, -, -, -, -, -, -	Ford #028-44	-
6700001000	A.M.S. w/handles 1"	EA
	Ford #KV23-444-HT-4	
6700002020	Meter adapter, brass 1-1/2" - 1"	EA
	Ford #A46	
6700135000	Coupling, compression 1"	EA
	Ford #C84-44	
6700145000	Corporation stop, cop 2"	EA
	Ford #F-600-7	
6700117000	Coupling, cop-cop 2"	EA

	Ford #C22-77	1
67001400100	Coupling, cop-iron 2": Ford #C28-77	EA
6700120000	Coupling, cop 2" Ford #C44-77	EA
6700158010	Curb stop, cop 2" Ford #B22-777	EA
6700158020	Curb stop, iron 2" Ford #B11-777	EA
6700002030	Meter adapter, brass " to 1" Ford #A47	EA
6700002060	Coupling, flanged " Ford #CF31-77	EA
8800000000	Gasket, 3/4", 100 per box Ford #GT-114	: EA

.

EXHIBIT A CHECKLIST OF ITEMS REQUIRED FOR SUBMISSION OF PROPOSAL 17-564

Vendors must complete this sheet and submit with their bid, along with the following items:

	Checklist form
	Cost information
	o Completion of Bid Analysis forms – Exhibit D
	Capacity information
—	o Vendor has to provide information on their capacity to perform the work outlined in the proposal
	Experience and qualifications
	Describe experience your company has in providing similar services (include number of years).
	 Identify all subcontractors (if applicable) and provide same information as proposed vendor.
	Vendor is to include the name of the landfill in which waste and compost will be disposed for the
	period of this contract. The City may request financial information of said landfill at a later date. o Describe how your company meets or exceeds the minimum qualification of the services
	requested.
	References
	 Supply at least three (3) references of municipalities (city, county, township, etc.) or communities (or developments) that are similar in size to this request. Please include customer's name, dates of
	contracts, summary of services provided, reference contact name, phone number, and address.
	Other
	Any information that the vendor would like to submit with their proposal
	Bid bond
	Completion of Collusion Form - Exhibit B
	Completion of Bid Form and Affidavits – Exhibit C
	Complete and submit requested information (documents) in Exhibit E
	(Vendor must submit DBE Utilization Good Faith Efforts Worksheet as
	part of bid submission. Document can be found in Exhibit E Attachment
	1)

Please note: failure to submit the above items will result in a rejection of your bid.

EXHIBIT B

Non-Collusion Affidavit

State of	w. ·	_:		
		s.s.		
County of $_$	·	_;		
Lete	te that I am	-£		
1 310	rte triat i arri		(Name of Firm)	
and that I ar	•	•	alf of my Firm, its Owner, Dire	ctors and Officers
			and the amount of the bid.	ctors and Officers.
um are pers	on responsible in my	min for the price(s)	and the amount of the blu.	
l sta	te that:			
1.			id have been arrived at indepe	•
		tion, communication	or agreement with any other	contractor, bidder o
	potential bidder.			
2.			f the bid, and neither the appr	•
			ave been disclosed to any other	•
		r potentiai bidder, ar	nd they will not be disclosed be	етоге тпе ріа
3.	opening.	oon mada ar will ba	made to induce any firm or pe	roon to rofrain from
J.	•		a bid higher than this bid, or to	
	_		or other form of complementa	•
4.			th and not pursuant to any ag	
			any firm or person to submit a	
			to submit a complementary or	
	bid.		,	•
5.		, its	affiliates, subsidiaries, officer	s, directors and
	employees are no	ot currently under in	vestigation by any governmen	tal agency and have
		· ·	ed or found liable for any act p	•
			living conspiracy or collusion w	vith respect to
	bidding on any pu	ublic contract, except	t as follows:	
				
		····		
	•			
		· · ·	····	

I state that	understands and	
(Name of my Fir	rm)	
Acknowledges that the above represents City of Flint in awarding the contract(s) founderstands that misstatement in this af the City of Flint of the true facts relating	or which this bid is submitted. I under ffidavit is and shall be treated as fraudo	stand and my firm ulent concealment from
		`
	(Signature)	
	(Printed Name)	
	(Position/Job Title)	
Notary Seal:		

EXHIBIT C

BID FORM

Replacement of Lead Service Lines

ARTICLE 1 - BID RECIPIENT

1.1	This Bid is submitted to:
	City of Flint
	1011 S. Saginaw St.
	Flint, MI 48502
1.2	The undersigned Bidder proposes and agrees, if this Bid is accepted, to enter into an Agreement with Owner in the form included in the Bidding Documents to perform all Work as specified or indicated in the Bidding Documents for the prices and within the times indicated in this Bid and in accordance with the other terms and conditions of the Bidding Documents.
ARTICL	E 2 – BIDDER'S ACKNOWLEDGEMENTS
2.1	Bidder accepts all of the terms and conditions of the Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. This Bid will remain subject to acceptance for 120 days after the Bid opening, or for such longer period of time that Bidder may agree to in writing upon request of Owner.
ARTICL	E 3 – BIDDER'S REPRESENTATIONS
3.1	In submitting this Bid, Bidder represents that:

- - A. Bidder has examined and carefully studied the Bidding Documents, and any data and reference items identified in the Bidding Documents, and hereby acknowledges receipt of the following Addenda:

<u>Addendum No.</u>	Addendum, Date

- B. Bidder has visited the area, conducted a thorough, alert visual examination of the complete areas, and become familiar with and satisfied itself as to the general, local, and area conditions that may affect cost, progress, and performance of the Work.
- C. Bidder is familiar with and has satisfied itself as to all Laws and Regulations that may affect cost, progress, and performance of the Work.
- D. Bidder has considered the information known to Bidder itself; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Bidding Documents; and any

Site-related reports and drawings identified in the Bidding Documents, with respect to the effect of such information, observations, and documents on (1) the cost, progress, and performance of the Work; (2) the means, methods, techniques, sequences, and procedures to be employed by Bidder; and (3) Bidder's safety precautions and programs.

- E. Bidder agrees, based on the information and observations referred to in the preceding paragraph, that no further examinations, investigations, explorations, tests, studies, or data are necessary for the determination of this Bid for performance of the Work at the price bid and within the times required, and in accordance with the other terms and conditions of the Bidding Documents.
- F. Bidder is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Documents.
- G. The Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance and furnishing of the Work.
- H. The submission of this Bid constitutes an incontrovertible representation by Bidder that Bidder has complied with every requirement of this Article, and that without exception the Bid and all prices in the Bid are premised upon performing and furnishing the Work required by the Bidding Documents.

ARTICLE 4 - BIDDER'S CERTIFICATION

4.1 Bidder certifies that:

- A. This Bid is genuine and not made in the interest of or on behalf of any undisclosed individual or entity and is not submitted in conformity with any collusive agreement or rules of any group, association, organization, or corporation;
- B. Bidder has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid;
- C. Bidder has not solicited or induced any individual or entity to refrain from bidding; and
- D. Bidder has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for the Contract. For the purposes of this Paragraph 4.01.D:
 - 1. "corrupt practice" means the offering, giving, receiving, or soliciting of anything of value likely to influence the action of a public official in the bidding process;
 - 2. "fraudulent practice" means an intentional misrepresentation of facts made (a) to influence the bidding process to the detriment of Owner, (b) to establish bid prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;
 - 3. "collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish bid prices at artificial, non-competitive levels; and
 - 4. "coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the e execution of the Contract.

(Name of my Fir Acknowledges that the above representative City of Flint in awarding the contract(s) for understands that misstatement in this afthe City of Flint of the true facts relating	ations are material and important, an or which this bid is submitted. I unde fidavit is and shall be treated as frauc	erstand and my firm dulent concealment from
	(Signature)	_
-	(Printed Name)	-
	(Position/Job Title)	-

EXHIBIT D BID ANALYSIS FORM


VENDORS MUST COMPLETE THESE SECTIONS


SUBCONTRACTOR LIST – LIST ALL SUBCONTRACTORS THAT WILL BE UTILIZE FOR THIS PROJECT AND THE SERVICES THAT WILL BE PROVIDED BY SAID SUBCONTRACTOR:


Name and Address of Subcontractor:	Services provided:


WATER SERVICE LINE REPLACEMENT ZONES -


- 1. There are 9 zones of approximately 600 replacement addresses that are outlined on attached maps and attachment which are included in this document. Work performed at each address could vary depending on the composition of water service line from the main to curb stop and curb stop to home.
- 2. Approximate zone locations, actual addresses and expected service line material makeup are provided. This data is provided for informational purposed only and the City cannot guarantee the accuracy of the service line materials listed or the status of a home until the time of replacement.
- 3. Locations may be removed by the City of Flint if new information deems replacement at those addresses impossible or unnecessary. The contractor will be notified by the City as soon as that information is available. The City may offer replacement addresses in the same vicinity.
- 4. Zones #3 and #6 All locations along the CRIM path shall be completed by June 26 to allow the City adequate time to restore the areas.
- 5. Zone #8 Fenton Road in this area will be under construction beginning mid-late Summer 2017. Contractor shall coordinate work to ensure no residents are trapped between work zones.
- 6. Contractors are expected to perform replacement work located within a zone if notified prior to completing all work in that zone even if the contractor has left that immediate block or area at no additional compensation. i.e. Permission is obtained for a replacement after the contractor has completed that block.


























All bids shall include all work necessary, as detailed in this document, to excavate, install and restore service lines at the prices penned below.

Construction Example – The construction of an "Average" Full Replacement would consist of excavating, installing 30' of pipe from Curb Stop to main, installing 40' of pipe from Curb Stop to residential home connecting to water meter, installing of new curb stop with fittings and stop box, curb cut (10'X10'), proper testing/flushing performed to validate site operational, backfilling and restoration.

The assigned locations will be a mixture of partial (curb stop to home or watermain) and full (watermain to home) replacements. Every type of installation will require a new curb stop and box. Payment will be determined by the type of installation - full (watermain to meter at the home) or partial (the watermain to the curb stop or curb stop to meter for a private side partial). There will be no additional payment for varying lengths. Each bid includes the service line, curb stop & box, and any necessary connections/adaptors to make the connections at the watermain, curb stop and house, depending on if it is a full replacement or a partial. Service lines 1.5" and greater include a new corporation and re-tapping of the watermain. No allowance for varying difficulty of installation, material costs, etc. will be granted unless specifically listed or stated in this RFP.

		Cost per Locat	ion for Water Service Lit	ne Replacement	
Ī	Zone 1	Zone 2	Zone 3	Zone 4	Zone 5
3/4" Partial					· · · · · · · · · · · · · · · · · · ·
Replacement					
3/4" Fuli					
Replacement					
3/4" Pipe Provided*					
Partial Replacement			•		
3/4" Pipe Provided*		<u> </u>			
Full Replacement					
1" Partial					
Replacement					
1" Full Replacement					
1.5" Partial					
Replacement					
1.5" Full					
Replacement					
2" Partial					
Replacement					
2" Full Replacement		3334			_

^{*} Bid Item as if the City of Flint will provide all 3/4" Type K Copper pipe. All other materials to be provided by the contractor.

You may be awarded none, some, or all of the zones that you bid above. If you are	
awarded multiple zones, what is the maximum number of zones that you are willing to	ZONES
accept and capable of completing in conformance with the requirements of this	ZONES
document?	

	Cos	t per Location for Wate	r Service Line Replacen	nent
	Zone 6	Zone 7	Zone 8	Zone 9
3/4" Partial				
Replacement				
3/4" Full				
Replacement				
3/4" Pipe Provided*			:	
Partial Replacement				
3/4" Pipe Provided*				
Full Replacement				
1" Partial				
Replacement				
1" Full Replacement				
1.5" Partial				
Replacement		·		
1.5" Full				
Replacement				
2" Partial				
Replacement				
2" Full Replacement				

Description	Price per Unit		
Cut and Cap Service Line of an Abandoned House	\$	/per Home	

^{**} Note: This pay item is to be used if a contractor encounters an abandoned house lead while excavating at the main to replace the service line of another home. The excavation and backfill is paid for through the line replacement pay item for the other lead. This item only includes cutting and capping an already exposed service.

Description	Price per Unit	
Excavate and Backfill a Standard Line	\$	/per Unit
** Note: This pay item is to be used if a contractor encounters a copper line when excavating for replacement. No line replacement is performed. A new curb box is placed and the excavation is backfilled and restored as this pay item.		

Description	Price per Unit	
Repair a Broken Sanitary Lead	\$	/per Unit
** Note: This pay item is to be used if a sanitary lead is broken through no fault o	of the contractor	

Description	Price per Unit	
Remove and Dispose of Contaminated Soil	\$	/per Syd
** Note: This pay item is to be used if contaminated soil is encountered		

Description	Price per Unit	
Please provide the Discount per Location if the City were to make the initial contact with the residents and obtain the consents from the Property Owners and Residents. The contractor would still be responsible for all other communications.	* \$	Less /per Home

Description	Pr	ice per Unit
Tree Removal: 1-6" Diameter	\$	/per Each
Tree Removal: 7-12" Diameter	\$	/per Each
Tree Removal: 13-24" Diameter	\$	/per Each
Tree Removal: 25-36" Diameter	\$	/per Each
Tree Removal: Over 36" Diameter	\$	/per Each
** Tree Prices include removal of the tree, necessary roots, stump and restorati	on of the yard to grade.	·

Certification Form Note

THIS PAGE MUST BE COMPLETED AND INCLUDED WITH THE SUBMITTAL: The undersigned hereby certifies, on behalf of the respondent named in this Certification (the "Respondent"), that the information provided in this offer submitted to the City of Flint is accurate and complete, and that I am duly authorized to submit same. I hereby certify that the Respondent has reviewed all documents and requirements included in this offer and accept its terms and conditions.

Fed. ID #:	
COMPANY NAME (Res	pondent):
ADDRESS	; <u> </u>
CITY/STATE/ZIP	; <u> </u>
PHONE	:FAX:
E-MAIL	:
PRINT NAME and Title	<u> </u>
	(Authorized Representative)
SIGNED	:
	(Authorized Representative)

EXHIBIT E

VENDORS MUST READ AND COMPLETE THE DOCUMENTS IN THIS SECTION. DOCUMENTS THAT ARE COMPLETED MUST BE INCLUDED WITH SUBMISSION.

REQUIRED STANDARD CONTRACT LANGUAGE: CLEAN WATER STATE REVOLVING FUND AND DRINKING WATER REVOLVING FUND

- Davis-Bacon/Prevailing Federal Wages, Including Labor Standards Provisions
- Disadvantaged Business Enterprise (DBE) Requirements*
- Debarment/Suspension Certification*

^{*} Bidders should note these sections contain instructions regarding forms/information that must be completed/included with any submitted bid.

Davis-Bacon/Prevailing Federal Wage Rates

P.L. 111-88 requires compliance with the Davis Bacon Act and adherence to the current U.S. Department of Labor Wage Decision. Attention is called to the fact that not less than the minimum salaries and wages as set forth in the Contract Documents (see Wage Decision included herein) must be paid on this project. The Wage Decision, including modifications, must be posted by the Contractor on the job site. A copy of the Federal Labor Standards Provisions is included and is hereby a part of this contract.

General Decision Number: MI170057 02/03/2017 MI57

Superseded General Decision Number: MI20160057

State: Michigan

Construction Type: Heavy

County: Genesee County in Michigan.

Heavy, Includes Water, Sewer Lines and Excavation (Excludes Hazardous Waste Removal; Coal, Oil, Gas, Duct and other similar Pipeline Construction)

Note: Under Executive Order (EO) 13658, an hourly minimum wage of \$10.20 for calendar year 2017 applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2015. If this contract is covered by the EO, the contractor must pay all workers in any classification listed on this wage determination at least \$10.20 (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in calendar year 2017. The EO minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Modification Number

Publication Date

0

01/06/2017

1

02/03/2017

CARP0706-017 08/01/2016

Rates	Fringes	
\$ 24.94	19.91	
Rates	Fringes	
\$ 35.40	20.94	
	\$ 24.94 	\$ 24.94 19.91 Rates Fringes

ENGI0325-019 06/01/2016

POWER EQUIPMENT OPERATORS: Underground Construction (Including Sewer)

	Rates	Fringes
POWER EQUIPMENT OPERATOR		
GROUP 1\$	31.58	22.85
GROUP 2\$	26.85	22.85
GROUP 3\$	26.12	22.85

GROUP 4.....\$ 25.55

22.85

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Backhoe/ Excavator, Boring Machine, Bulldozer, Crane, Grader/ Blade, Loader, Roller, Scraper, Trencher (over 8 ft. digging capacity)

GROUP 2: Trencher (8-ft digging capacity and smaller)

GROUP 3: Boom Truck (non-swinging, non- powered type boom)

GROUP 4: Broom/ Sweeper, Fork Truck, Tractor, Bobcat/ Skid Steer /Skid Loader

ENGI0326-011 06/01/2014

EXCLUDES UNDERGROUND CONSTRUCTION

	I	Rates	Fringes
OPERATOR:	Power Equipment		
Group	1\$	29.09	21.70
Group	2\$	28.84	21.70
Group	3\$	27.74	21.70
Group	4\$	22.94	21.70
Group	5\$	22.34	21.70
Group	6\$	19.89	21.70

FOOTNOTES:

Crane operator with main boom and jib 300' or longer: \$1.50 per hour above the group 1 rate.

Crane operator with main boom and jib 400' or longer: \$3.00 per hour above the group 1 rate.

PAID HOLIDAYS: New Year's Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day and Christmas Day.

POWER EQUIPMENT OPERATOR CLASSIFICATIONS

GROUP 1: Crane operator with main boom and jib 400', 300', or 220' or longer.

GROUP 2: Crane operator with main boom and jib 140' or longer, tower crane, gantry crane, whirley derrick

GROUP 3: Backhoe/Excavator; Boring Machine; Bulldozer; Crane; Grader/Blade; Loader; Roller; Scraper; Tractor; Trencher

GROUP 4: Bobcat/Skid Loader; Broom/Sweeper; Fork Truck (over 20' lift)

GROUP 5: Boom truck (non-swinging)

GROUP 6: Fork Truck (20' lift and under for masonry work)

IRON0025-006 06/01/2015

	Rates	Fringes	
IRONWORKER			
Reinforcing	\$ 28.30	24.60	
Structural	\$ 33.78	27.84	

LABO0334-009 06/01/2015

EXCLUDES OPEN CUT CONSTRUCTION

	Rates	Fringes
Landscape Laborer		
GROUP 1	\$ 19.76	9.15
GROUP 2	\$ 15.54	9.15

LANDSCAPE LABORER CLASSIFICATIONS

GROUP 1: Landscape specialist, including air, gas and diesel equipment operator, lawn sprinkler installer and skidsteer (or equivalent)

GROUP 2: Landscape laborer: small power tool operator, material mover, truck driver and lawn sprinkler installer tender

LABO0334-015 09/01/2014

SCOPE OF WORK:

OPEN CUT CONSTRUCTION: Excavation of earth and sewer, utilities, and improvements, including underground piping/conduit (including inspection, cleaning, restoration, and relining)

	Rates	Fringes
LABORER		
 Common or General 	\$ 20.64	12.75
(2) Mason Tender-		
Cement/Concrete	\$ 20.78	12.75
(4) Grade Checker	\$ 20.95	12.75
(5) Pipelayer	\$ 21.09	12.75
(7) Landscape	\$ 15.54	12.75

LABO1075-010 06/01/2016

EXCLUDES OPEN CUT CONSTRUCTION

Rates Fringes

LABORER

13.28

Fringes

Common or General; Grade Checker; Mason Tender -

Cement/Concrete; Pipelayer..\$ 22.51

PAIN1052-003 06/01/2016

	Rates	Fringes	
PAINTER			
Brush & Roler	\$ 24.45	11.25	
Spray	\$ 25.80	11.25	

PLAS0016-016 04/01/2014

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER.	\$ 25.58	12.88

PLUM0370-006 06/01/2016

	Rates	Fringes
PLUMBER/PIPEFITTER	\$ 36.11	19.65
		

* TEAM0007-006 06/01/2016

TRUCK DRIVER	
Dump Truck under 8 cu.	
yds.; Tractor Haul Truck\$ 24.90	.50 + a+b
Dump Truck, 8 cu. yds. and	
over\$ 25.00	.50 + a+b
Lowboy/Semi-Trailer Truck\$ 25.15	.50 + a+b

Rates

FOOTNOTE:

- a. \$438.45 per week.
- b. \$61.90 daily.

SUMI2010-055 11/09/2010

	Rates	Fringes
TRUCK DRIVER: Off the Road Truck\$	20.82	3.69
~		

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide

employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of "identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than "SU" or "UAVG" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the "SU" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that

classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

29 CFR Part 5 - Labor Standards Provisions for Federally Assisted Projects

§ 5.5 Contract provisions and related matters.

- (a) The Agency head shall cause or require the contracting officer to insert in full in any contract in excess of \$2,000 which is entered into for the actual construction, alteration and/or repair, including painting and decorating, of a public building or public work, or building or work financed in whole or in part from Federal funds or in accordance with guarantees of a Federal agency or financed from funds obtained by pledge of any contract of a Federal agency to make a loan, grant or annual contribution (except where a different meaning is expressly indicated), and which is subject to the labor standards provisions of any of the acts listed in Sec. 5.1, the following clauses (or any modifications thereof to meet the particular needs of the agency, *Provided*, That such modifications are first approved by the Department of Labor):
- (1) Minimum wages. (i) All laborers and mechanics employed or working upon the site of the work (or under the United States Housing Act of 1937 or under the Housing Act of 1949 in the construction or development of the project), will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (a)(1)(iv) of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in Sec. 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph (a)(1)(ii) of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

- (ii)(A) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
- (1) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

- (2) The classification is utilized in the area by the construction industry; and
- (3) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (B) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (C) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (D) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs (a)(1)(ii) (B) or (C) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- (iii) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- (iv) If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- (2) Withholding. The (write in name of Federal Agency or the loan or grant recipient) shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld from the contractor under this contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work (or under the United States Housing Act of 1937 or under the Housing Act of

1949 in the construction or development of the project), all or part of the wages required by the contract, the (Agency) may, after written notice to the contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

- (3) Payrolls and basic records. (i) Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work (or under the United States Housing Act of 1937, or under the Housing Act of 1949, in the construction or development of the project). Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.
- (ii)(A) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the (write in name of appropriate federal agency) if the agency is a party to the contract, but if the agency is not such a party, the contractor will submit the payrolls to the applicant, sponsor, or owner, as the case may be, for transmission to the (write in name of agency). The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at http://www.dol.gov/whd/forms/wh347.pdf or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the (write in name of appropriate federal agency) if the agency is a party to the contract, but if the agency is not such a party, the contractor will submit them to the applicant, sponsor, or owner, as the case may be, for transmission to the (write in name of agency), the contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the sponsoring government agency (or the applicant, sponsor, or owner).
- (B) Each payroll submitted shall be accompanied by a ``Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

- (1) That the payroll for the payroll period contains the information required to be provided under Sec. 5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under Sec. 5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;
- (2) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;
- (3) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- (C) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph (a)(3)(ii)(B) of this section.
- (D) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.
- (iii) The contractor or subcontractor shall make the records required under paragraph (a)(3)(i) of this section available for inspection, copying, or transcription by authorized representatives of the (write the name of the agency) or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the Federal agency may, after written notice to the contractor, sponsor, applicant, or owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.
- (4) Apprentices and trainees--(i) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its

program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

- (ii) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (iii) Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.
- (5) Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.
- (6) Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses contained in 29 CFR 5.5(a)(1) through (10) and such other clauses as the (write in the name of the Federal agency) may by appropriate instructions require, and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.

- (7) Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- (8) Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.
- (9) Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.
- (10) Certification of eligibility. (i) By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- (ii) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).
- (iii) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.
- (b) Contract Work Hours and Safety Standards Act. The Agency Head shall cause or require the contracting officer to insert the following clauses set forth in paragraphs (b)(1), (2), (3), and (4) of this section in full in any contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by Sec. 5.5(a) or 4.6 of part 4 of this title. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.
- (1) Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.
- (2) Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (b)(1) of this section the contractor and any subcontractor responsible there for shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (b)(1) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (b)(1) of this section.

- (3) Withholding for unpaid wages and liquidated damages. The (write in the name of the Federal agency or the loan or grant recipient) shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (b)(2) of this section.
- (4) Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (b)(1) through (4) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (b)(1) through (4) of this section.
- (c) In addition to the clauses contained in paragraph (b), in any contract subject only to the Contract Work Hours and Safety Standards Act and not to any of the other statutes cited in Sec. 5.1, the Agency Head shall cause or require the contracting officer to insert a clause requiring that the contractor or subcontractor shall maintain payrolls and basic payroll records during the course of the work and shall preserve them for a period of three years from the completion of the contract for all laborers and mechanics, including guards and watchmen, working on the contract. Such records shall contain the name and address of each such employee, social security number, correct classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. Further, the Agency Head shall cause or require the contracting officer to insert in any such contract a clause providing that the records to be maintained under this paragraph shall be made available by the contractor or subcontractor for inspection, copying, or transcription by authorized representatives of the (write the name of agency) and the Department of Labor, and the contractor or subcontractor will permit such representatives to interview employees during working hours on the job.

Disadvantaged Business Enterprises (DBE)

Prime contractors bidding on this project must follow, document, and maintain documentation of their Good Faith Efforts, as listed below, to ensure that Disadvantaged Business Enterprises (DBEs) have the opportunity to participate in the project by increasing DBE awareness of procurement efforts and outreach. Bidders must make the following Good Faith Efforts for any work that will be subcontracted.

- 1. Ensure DBEs are made aware of contracting opportunities to the fullest extent practicable through outreach and recruitment activities. Place DBEs on solicitation lists and solicit DBEs whenever they are potential sources.
- 2. Make information on forthcoming opportunities available to DBEs. Arrange time-frames for contracts and establish delivery schedules, where the requirements permit, in a way that encourages and facilitates participation by DBEs in the competitive process. Whenever possible, post solicitation for bids or proposals for a minimum of 30 calendar days before the bid or proposal closing date. The DBEs should be given a minimum of 5 days to respond to the posting.
- Consider in the contracting process whether firms competing for large contracts can be subcontracted with DBEs. Divide total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by DBEs in the competitive process.
- Encourage contracting with a consortium of DBEs when a contract is too large for one DBE firm to handle individually.
- 5. Use the services and assistance of the Small Business Administration and the Minority Business Development Agency of the U.S. Department of Commerce.

Subsequent to compliance with the Good Faith Efforts, the following conditions also apply under the DBE requirements. Completed Good Faith Efforts Worksheets (Attachment 1), along with the required supporting documentation outlined in the instructions, must be submitted with your bid proposal. EPA form 6100-2 must also be provided at the pre-bid meeting. A copy of this form is available on the Forms and Guidance page of the Revolving Loan website.

- 1. The prime contractor must pay its subcontractor for work that has been satisfactorily completed no more than 30 days from the prime contractor's receipt of payment from the owner.
- 2. The prime contractor must notify the owner in writing prior to the termination of any DBE subcontractor for convenience by the prime contractor and employ the Good Faith Efforts if soliciting a replacement contractor.
- If a DBE contractor fails to complete work under the subcontract for any reason, the prime contractor must employ the Good Faith Efforts if soliciting a replacement contractor.
- The prime contractor must employ the Good Faith Efforts.

Debarment Certification

The prime contractor must provide a completed **Certification Regarding Debarment**, **Suspension**, **and Other Responsibility Matters Form** with its bid or proposal package to the owner (Attachment 2).

Attachment 1

Disadvantaged Business Enterprise (DBE) Utilization GOOD FAITH EFFORTS WORKSHEET

	o ·		
	·		
•			
	•		
			·

Michigan Department of Environmental Quality Office of Drinking Water and Municipal Assistance-Revolving Loan Section Disadvantaged Business Enterprise (DBE) Utilization State Revolving Fund/Drinking Water Revolving Fund GOOD FAITH EFFORTS WORKSHEET

Bidder:

Subcontract Area of Work (one pe	er worksheet:				
Outreach Goal: Solicit a minimur sources be used to locate the minimum (MDOT) website and www.sam.g DBEs.	mum number	of DBEs. Tl	he Michigan De	partment of Tra	insportation
List the DBEs contacted for the ab DBE.	ove area of v	vork and com	plete the follow	ing information	n for each
Company Name	Type of Contact	Date of Contact	Price Quote Received	Accepted/ Rejected	Please Explain if Rejected
		<u> </u>		□ A	
				□ A	
<u> </u>				□ R	
	 		<u> </u>		
			-	$\square R$	
· · · · · · · · · · · · · · · · · · ·				$\Box A$	
e :				$\Box \mathbf{R}$	
Explanation for Not Achieving a Minimum of Three Contacts; you may include a printout of the MDOT and www.sam.gov search results (attach extra sheets if necessary):					
MITA DBE Posting Date (if applicattach a copy of the DBE advertise)				_	
Other Efforts (attach extra sheets i	f necessary):				
Please include the completed	worksheet a	nd supporti	ao documentat	ion with the hi	d proposal

DEQ

Rick Snyder, Governor

Rev.3-2015

Dan Wyant, Director

Michigan Department of Environmental Quality Office of Drinking Water and Municipal Assistance—Revolving Loan Section Disadvantaged Business Enterprise (DBE) Utilization State Revolving Fund/Drinking Water Revolving Fund GOOD FAITH EFFORTS WORKSHEET

Instructions to Bidders for the Completion of the Good Faith Efforts Worksheet

- 1. Separate worksheets must be provided for each area of work to be subcontracted out. This includes both major and minor subcontracts.
- 2. A minimum of three (3) DBEs must be contacted by a verifiable means of communication such as e-mail, letter, or fax for each area of work to be subcontracted out. Copies of the solicitation letters/e-mails and fax confirmation sheets must be provided with the worksheet.
- 3. If less that three (3) DBEs exist statewide for the area of work, then provide documentation that other DBE resources were consulted. This may include the MDOT and www.sam.gov registries and an advertisement is a publication. A printout of the website searched (conducted prior to the end of the bid period) must be submitted.
- 4. Posting solicitations for quotes/proposals from DBEs on the MITA website (www.mitadbe.com) is highly recommended to facilitate participation in the competitive process whenever possible. The solicitation needs to identify the project and the areas of work to be subcontracted out. A copy of the MITA DBE advertisement must be submitted with the Good Faith Efforts worksheet, if used, or a printout of the resulting quotes posted to the MITA website can be submitted with this form as supporting documentation.
- 5. If the area of work is so specialized that no DBEs exist, then an explanation is required to support that conclusion, including the documentation required in No. 3 above.
- 6. The date of the DBE contact must be identified, as it is important to document that the DBE solicitation was made during the bid period and that sufficient time was given for the DBE to return a quote.
- 7. Each DBE firm's price quote must be identified if one was received or N/A entered on the worksheet if a quote was not received. Copies of all quotes must be submitted with the worksheet.
- 8. If a quote was received, indicate if it was accepted or rejected. Justification for not accepting a quote and not using the DBE subcontractor must be provided.
- 9. Under Other Efforts, please indicate additional steps you have taken to obtain DBE contractors and provide the appropriate supporting documentation such as:
 - Follow-up e-mails, faxes, or letters.
 - Copies of announcements/postings in newspapers, trade publications, or minority media that target DBE firms.

Rev. 3-2015

Attachment 2

Certification Regarding Debarment, Suspension, and Other Responsibility Matters

Certification Regarding Debarment, Suspension, and Other Responsibility Matters

The prospective participant certifies, to the best of its knowledge and belief, that it and its principals:

- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in transactions under federal nonprocurement programs by any federal department or agency;
- (2) Have not, within the three year period preceding the proposal, had one or more public transactions (federal, state, or local) terminated for cause or default; and
- (3) Are not presently indicted or otherwise criminally or civilly charged by a government entity (federal, state, or local) and have not, within the three year period preceding the proposal, been convicted of or had a civil judgment rendered against it:
 - (a) For the commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public transaction (federal, state, or local) or a procurement contract under such a public transaction;
 - (b) For the violation of federal or state antitrust statutes, including those proscribing price fixing between competitors, the allocation of customers between competitors, or bid rigging; or
 - (c) For the commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property.

I understand that a false statement on this certification may be grounds for the rejection of this proposal or the termination of the award. In addition, under 18 U.S.C. §1001, a false statement may result in a fine of up to \$10,000 or imprisonment for up to five years, or both.

Name and Title of Authorized Representative	
Name of Participant Agency or Firm	
Signature of Authorized Representative	Date
☐ I am unable to certify to the above statement. Attache	ed is my explanation

Attachment 3

Frequently Asked Questions About Disadvantaged Business Enterprise (DBE) Solicitation

Disadvantaged Business Enterprise (DBE) Requirements Frequently Asked Questions Regarding Contractor Compliance

Q: What is the Good Faith Efforts Worksheet form and how is it to be completed?

A: This form captures efforts by the prime contractor to solicit DBEs for each area of work type that will be subcontracted out. A separate Good Faith Efforts Worksheet must be provided by the prime contractor for each area of work type to be subcontracted out. There are specific instructions that accompany this form that prescribe minimum efforts which bidders must make in order to be in compliance with the DBE requirements.

Q: Can non-certified DBEs be used?

A: While non-certified DBEs can be used, only DBEs, MBEs, and WBEs that are certified by EPA, SBA, or MDOT (or by tribal, state and local governments, as long as their standards for certification meet or exceed the standards in EPA policy) can be counted toward the fair share goal. Proof of certification by one of these recognized and approved agencies should be sought from each DBE.

Q: How does a DBE get certified?

A: Applications for certification under MDOT can be found at http://mdotjboss.state.mi.us/UCP/LearnHowServlet.

Applications for certification under EPA can be found on EPA's Small Business Programs website at http://www.epa.gov/osbp/dbe_firm.htm under Certification Forms.

Q: If a bidder follows the MDOT DBE requirements, will the bidder be in compliance with the SRF/DWRF DBE requirements?

A: No. Federally funded highway projects utilize DBE goals, which require that a certain percentage of work be performed by DBE subcontractors. For SRF/DWRF projects, there is no financial goal. However, there is a solicitation effort goal. Bidders must use Good Faith Efforts for each and every area of work to be subcontracted out to obtain DBEs. The bidders are not required to use DBEs if the quotes are higher than non-DBE subcontractors. There is no required DBE participation percentage contract goal for the SRF/DWRF. However, if the SRF/DWRF project is part of a joint project with MDOT, the project can be excluded from SRF/DWRF DBE requirements (i.e., the Good Faith Efforts Worksheet is not required) as it would be difficult to comply with both programs' requirements.

Q. Must the Good Faith Efforts Worksheet and supporting documentation be turned in with the bid proposals?

A: Yes. This is a requirement to document that the contractor has complied with the DBE requirements and the Good Faith Efforts. These compliance efforts must be done during the bidding phase and not after-the-fact. It is highly recommended that the need for these efforts and the submittal of the forms with the bid proposals be emphasized at the pre-bid meetings. Failure to show that the Good Faith Efforts were complied with during the bidding process can lead to a prime contractor being found non-responsive.

Q: Does EPA form 6100-2 need to be provided at the pre-bid meeting?

A: Yes. The form must be made available at the pre-bid meeting.

- Q: What kinds of documentation should a contractor provide to document solicitation efforts?
- **A:** Documentation can include fax confirmation sheets, copies of solicitation letters/e-mails, printouts of online solicitations, printouts of online search results, affidavits of publication in newspapers, etc.
- Q: How much time will compliance with the Good Faith Efforts require in terms of structuring an adequate bidding period?
- A: Due to the extent of the efforts required, a minimum of 30 calendar days is recommended between bid posting and bid opening to ensure adequate time for contractors to locate certified DBEs and solicit quotes.
- Q: How does a contractor locate certified DBEs?
- A: The Michigan Department of Transportation has a directory of all Michigan certified entities located at http://mdotjboss.state.mi.us/UCP/. Additionally, the federal System for Award Management (SAM) is another place to search and can be found at www.sam.gov. SAM contains information from the former Central Contractor Registration (CCR) database.
- **Q:** If the bidder does not intend to subcontract any work, what forms, if any, must be provided with the bid proposal?
- A: The bidder should complete the Good Faith Efforts Worksheet with a notation that no subcontracting will be done. However, if the bidder is awarded the contract and then decides to subcontract work at any point, then the Good Faith Efforts must be made to solicit DBEs.
- Q: In the perfect world, the Good Faith Efforts Worksheet is required to be turned in with the proposal. What if no forms are turned in with the bid proposal or forms are blank or incomplete? Should this be cause to determine that the bidder is non-responsive?
- A: While the Good Faith Efforts Worksheet is important, it is more critical to confirm that the contractor complied with the DBE requirements prior to bid opening. The owner should contact the bidder as soon as deficiencies are noted for a determination/documentation of efforts taken to comply with the DBE requirements. Immediate submittal of the completed forms will be acceptable provided the Good Faith Efforts were made and it is just a matter of transferring information to the forms.
- Q: If the prime contractor is a DBE, does he have to solicit DBE subcontractors?
- A: Yes, the DBE requirements still apply if the prime intends to subcontract work out. Good Faith Efforts must be used to solicit DBEs.
- Q: If the area of work is one where there are less than three DBE contractors, how is the contractor to document this?
- A: Copies of printouts from MDOT and SAM showing no DBEs and advertisements soliciting quotes for all subcontract areas, including the questionable areas, will be adequate if the dates on the printouts are prior to the bid or proposal closing date.